


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT



<b>APPLICATION FOR PERMIT TO DRILL</b>						<b>1. WELL NAME and NUMBER</b> Desert Springs State 412-36-9-18				
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						<b>3. FIELD OR WILDCAT</b> 8 MILE FLAT NORTH				
<b>4. TYPE OF WELL</b> Gas Well <input type="checkbox"/> Coalbed Methane Well: NO <input type="checkbox"/>						<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b>				
<b>6. NAME OF OPERATOR</b> GASCO PRODUCTION COMPANY						<b>7. OPERATOR PHONE</b>				
<b>8. ADDRESS OF OPERATOR</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112						<b>9. OPERATOR E-MAIL</b>				
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> ML45171			<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>				
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>				
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>				
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>			<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			<b>19. SLANT</b> VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
<b>20. LOCATION OF WELL</b>		<b>FOOTAGES</b>		<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>	<b>RANGE</b>	<b>MERIDIAN</b>		
LOCATION AT SURFACE		1462 FNL 1352 FEL		SWNE	36	9.0 S	18.0 E	S		
Top of Uppermost Producing Zone		495 FNL 660 FEL		NENE	36	9.0 S	18.0 E	S		
At Total Depth		495 FNL 660 FEL		NENE	36	9.0 S	18.0 E	S		
<b>21. COUNTY</b> UINTAH			<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 495			<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 640				
			<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 1000			<b>26. PROPOSED DEPTH</b> MD: 12885 TVD: 12700				
<b>27. ELEVATION - GROUND LEVEL</b> 4912			<b>28. BOND NUMBER</b> K08792707			<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> 41-3530				
<b>Hole, Casing, and Cement Information</b>										
<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Length</b>	<b>Weight</b>	<b>Grade &amp; Thread</b>	<b>Max Mud Wt.</b>	<b>Cement</b>	<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>
COND	17.25	13.375	0 - 60	48.0	H-40 ST&C	8.3	Class G	55	1.18	15.8
SURF	12.25	9.625	0 - 3400	36.0	J-55 LT&C	8.3	Hi Lift "G"	290	3.91	11.0
							Premium Foamed	115	1.63	14.2
PROD	8.75	4.5	0 - 12885	13.5	HCP-110 LT&C	11.6	Premium Lite High Strength	680	2.26	12.0
							50/50 Poz	2090	1.31	14.3
<b>ATTACHMENTS</b>										
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
<b>NAME</b> Roger Knight				<b>TITLE</b> EHS Supervisor			<b>PHONE</b> 303 996-1803			
<b>SIGNATURE</b>				<b>DATE</b> 11/19/2012			<b>EMAIL</b> rknight@gascoenergy.com			
<b>API NUMBER ASSIGNED</b> 43047533240000				<b>APPROVAL</b>  Permit Manager						

RECEIVED: March 12, 2013

**Gasco Production Company**  
**Desert Springs State 412-36-9-18**  
**NE/NE, Section #36, Township 9 South, Range 18 East**  
**Uintah County, Utah**  
**Lease No. ML-45171**

**Drilling Program**

**1. Estimated Tops of Important Geological Markers**

<b>Formation</b>	<b>Depth</b>	<b>Subsea</b>
Wasatch	5165'	-110
Mesaverde	9055'	-4000'
Castlegate	11455'	-6400'
Blackhawk	11705'	-6650'
Spring Canyon	12365'	-7310'
TD	12885'	

**2. Estimated Depth of Anticipated Water, Oil, Gas or Mineral Formations**

<b>Substance</b>	<b>Formation</b>	<b>Depth</b>
Gas	Wasatch	5165' - 9054'
Gas	Mesaverde	9055' - 11454'
Gas	Blackhawk	11705' - 12364'
Gas	Spring Canyon	12365' - 12855'

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

**3. Pressure Control Equipment**

All well control equipment will be in accordance to UDOGM Conservation Rules for 5M Systems and are as follows:

5,000# BOP with 4 ½" Pipe Rams  
 5,000# BOP with Blind Rams  
 5,000# Annular

Ram type preventers and associated equipment shall be tested to the approved stack working pressure if isolated by test plug or to 70 percent of internal yield pressure of casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. If a test plug is utilized, no bleed-off pressure is acceptable. For a test not utilizing a test plug, if a decline on pressure of more than 10 percent in 30 minutes occurs, the test shall be considered to have failed. Valve on casing head below test plug shall be open during test of BOP stack.

**Pressure Control Equipment Continued**

Annular type preventers (if used) shall be tested to 50 percent of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

As a minimum, the above test shall be performed:

- a. when initially installed;
- b. whenever any seal subject to test pressure is broken
- c. following related repairs; and
- d. at 30 day intervals

Valves shall be tested from working pressure side during BOPE tests with all down stream valves open.

When testing the kill line valve(s) the check valve shall be held open or the ball removed.

Annular preventers shall be functionally operated at least weekly.

Pipe and blind rams shall be activated each trip, however, this function need not be performed more than once a day.

A BPOPE pit level drill shall be conducted weekly for each drilling crew.

Pressure tests shall apply to all related well control equipment.

All of the above described tests and/or drills shall be recorded in the drilling log.

BOP systems shall be consistent with API RP 53 Pressure tests will be conducted before drilling out from under casing strings which have been set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection will be recorded on the daily drilling report. Preventers will be pressure tested before drilling cement plugs.

A rotating head will be utilized to set surface casing as in the casing and string design. This would be used as a diverter.

UDOGM will be notified, with sufficient lead time, in order to have a UDGOM representative on location during testing.

- a. The size and rating of the BOP stack is shown on the attached diagram. Although a rig has not yet been chosen to drill this well, most of the equipment for this depth will utilize 5M working BOP.
- b. A choke line and kill line are to be properly installed. The kill line is not to be used as a fill-up line.
- c. The accumulator system shall have a pressure capacity to provide for repeated operation of hydraulic preventers.
- d. Drill string safety valve(s), to fit all tools in the drill string, are to be maintained on the rig floor while drilling operations are in progress.



#### 4. Proposed Casing and Cementing Program

a. The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones abnormally pressured zones and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation which will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors including: presence/absence of hydrocarbons, fracture gradients, usable water zones, formation pressures, lost circulation zones, other minerals, or other unusual characteristics. All indications of usable water shall be reported.

##### b. Casing Program

	<u>Depth</u>	<u>Hole Size</u>	<u>O.D.</u>	<u>Grade</u>	<u>Weight</u>	<u>Type</u>
Conductor	60'	17.25"	13.375"	H-40	48#	-
Surface	3400'	12.25"	9.625"	J-55	36#	LTC
Production	12885'	8.75"	4.5"	HCP-110	13.5#	LTC

c. Casing design subject to revision based on geologic conditions encountered.

##### d. Cement Program

	<u>Top of Cement</u>	<u>Sacks</u>	<u>Cement Type</u>	<u>Yield</u>	<u>Supply Wt.</u>
Conductor	To surface	55	Class G	1.18	15.8
Surface	To surface	290	Hi-Lift	3.91	11.0
		115	RFC	1.63	14.2
Production	To surface	680	Premium Lite	2.26	12.0
		2090	50/50 poz	1.31	14.3

e. Anticipated cement tops will be reported as to depth; not the expected number of sacks of cement to be used. UDOGM should be notified, with sufficient lead time, in order to have a UDOGM representative on location while running all casing strings and cementing.

f. After cementing but before commencing any test, the casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the driller's log.

g. The following reports shall be filed with UDOGM within 30 days after the work is completed.

1. Progress reports, per UDOGM Conservation General Rules "Sundry Notices and Reports on Wells", must Include complete information concerning:

a. Setting of each string of casing, showing the size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing,



depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.

b. Temperature or bond log must be submitted for each well where the casing cement was not circulated to the surface.

c. Auxiliary equipment to be used is as follows:

1. Kelly cock
2. A bit float
3. A sub with full opening valve.

## 5. Drilling Fluids Program:

<u>Interval Type</u>		<u>Wt. (ppg)</u>	<u>Viscosity</u>	<u>pH</u>	<u>Water Loss</u>	<u>Remarks</u>
0-60'	Air Mist	8.3	1	7.0	NA	
60'-3400'	AirMist	8.3	35	7.0	NA	
3400'-TD	Water based mud	8.3- 11.6	35	10-10.5		

a. Sufficient quantities of mud material will be maintained on site or be readily available for the purpose of assuring well control. SPR will be recorded on a daily drilling report after mudding up. Visual mud monitoring will be conducted during operations.

b. No chromate additives will be used in the mud system on State lands without prior UDOGM approval to ensure adequate protection of fresh water aquifers.

c. No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well.

d. The use of materials under UDOGM jurisdiction will conform to the Conservation General Rules.

e. Water will come from: Water Right No. 41-3530.

f. Water will be hauled by commercial transport over the access roads shown on Attached Maps "A" and "B".

g. No water well will be drilled on this lease

## 6. Evaluation Program

The anticipated type and amount of testing, logging and coring are as follows:

a. No drill stem tests are anticipated, if DST's are run, the following requirements will be adhered to:

Initial opening of the drill stem test tools shall be restricted to daylight hours unless specific approval to start during other hours is obtained from the authorized officer (AO). However, DST's may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e. lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping shall not begin before daylight, unless prior approval is obtained from the AO. Closed chamber DST's may be accomplished day or night.

A DST that flows to the surface with evidence of hydrocarbons shall be either reversed out of the testing string under controlled surface conditions. This would involve provided means for reverse circulation.

Separation equipment required for the anticipated recovery shall be properly installed before a test starts.

All engines within 100 feet of the wellbore that are required to "run" during the test shall have spark arresters or water cooled exhausts.

b. The logging program will consist of Schlumberger Platform Express (or equivalent) to be run from base of surface casing to TD.

c. No cores are anticipated.

d. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" will be submitted no later than 30 days after the completion of the well or after completion of operations being performed, in accordance with UDOGM Conservation General Rules. Two copies of all logs, core descriptions, core analyses, well tested data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed.

Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

e. The anticipated completion program is as follows: Perform multistage fracs and complete all productive zones present in the wellbore. Produce all zones commingled.

f. Daily drilling and completion progress reports shall be submitted to the UDOGM on a weekly basis.

## **7. Abnormal Temperatures and Pressures**

a. The expected bottom hole pressure is 7655psig

The maximum bottom hole temperature anticipated is 230 degrees Fahrenheit.

b. No hydrogen sulfide gas is anticipated. Abnormal pressures will be controlled with mud weight and 5000# BOP and rotating head.

## **8. Anticipated Starting Dates and Notifications of Operations**

a. Drilling is anticipated to commence immediately upon approval

b. It is anticipated that the drilling of this well will take approximately 15 days.

c. UDOGM shall be notified of the anticipated date of location construction and anticipated spud date.



- d. No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior to approval from the AO will be obtained and notification given before resuming operations.
- e. The spud date will be reported orally to the AO within 48 hours of spudding. If the spudding occurs on a weekend or holiday, the report will be submitted via voice mail and/or e-mail to the AO.
- f. In accordance with UDOGM Conservation General Rules, this well will report "Monthly Report Operations", starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report will be filed with the UDOGM.
- g. Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual or undesirable events shall be reported promptly to the AO in accordance with the requirements.
- h. If a replacement rig is contemplated for completion operations, a "Sundry Notice" to that effect will be filed, or prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.
- i. Should the well be successfully completed for production, the AO will be notified when the well is placed on producing status. Written notification, e-mail or otherwise, will be sent no later than 5 days following the date on which the well is placed on production.
- j. With the approval of the UDOGM Engineer, produced water may be temporarily disposed of into unlined pits for a period of 90 days. During the period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the UDOGM Engineer.
- k. Operators are authorized to vent/flare gas during initial well evaluation test, not exceeding a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the UDOGM Engineer and approval received, for any venting/flaring of gas beyond the initial 30 day authorized test period.
- l. A schematic facilities diagram shall be submitted to UDOGM within 60 days of installation or first production whichever occurs first. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with UDOGM Conservation General Rules.
- m. A first production conference will be scheduled within 15 days after receipt of the first production notice.
- n. No well abandonment operations will commence without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" will be filed within 30 days following the completion of the well for abandonment. The report will indicate where plugs were placed and the current status of the surface restoration. Final abandonment will not be approved until the surface reclamation work has been completed to the satisfaction of the AO.



o. Lessees and operators have the responsibility of operating in a manner which conforms with the applicable Federal laws and regulations and with the State and local laws and regulations to the extent that such laws are applicable to operations on State lands.

Department of Natural Resources  
Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, Utah 84116

Phone 801-538-5340  
Fax 801-539-3940

**CONFIDENTIAL**

T9S, R18E, S.L.B.&M.

GASCO PRODUCTION COMPANY


Well location, DESERT SPRINGS STATE  
#412-36-9-18, located as shown in the SW 1/4  
NE 1/4 of Section 36, T9S, R18E, S.L.B.&M.,  
Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHWEST CORNER OF SECTION 14,  
T10S, R18E, S.L.B.&M., TAKEN FROM THE MOON BOTTOM  
QUADRANGLE, UTAH, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP)  
PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE  
INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS  
BEING 5129 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PROPERTY WAS PREPARED FROM  
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY  
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE  
BEST OF MY KNOWLEDGE AND BELIEF.




UINTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'  
DATE SURVEYED: 08-27-12  
DATE DRAWN: 08-28-12

PARTY J.F. D.D. T.B.  
REFERENCES G.L.O. PLAT


WEATHER HOT  
FILE GASCO PRODUCTION COMPANY




LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°59'35.79" (39.993275)	LATITUDE = 39°59'26.25" (39.990625)
LONGITUDE = 109°50'05.68" (109.834911)	LONGITUDE = 109°50'14.55" (109.837375)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°59'35.92" (39.993311)	LATITUDE = 39°59'26.38" (39.990661)
LONGITUDE = 109°50'03.16" (109.834211)	LONGITUDE = 109°50'12.03" (109.836675)





**LEGEND:**

————— EXISTING ROAD  
 - - - - - PROPOSED ACCESS ROAD

**GASCO PRODUCTION COMPANY**

DESERT SPRINGS STATE #314-36-9-18,  
 #412-36-9-18 & #424-36-9-18  
 SECTION 36, T9S, R18E, S.L.B.&M.  
 SW 1/4 NE 1/4




**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

ACCESS ROAD  
 MAP

08 29 12  
 MONTH DAY YEAR

**B**  
**TOPO**

SCALE: 1" = 2000' DRAWN BY: M.M. REVISED: 00-00-00

**LEGEND:**

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**GASCO PRODUCTION COMPANY**


DESERT SPRINGS STATE #314-36-9-18,  
#412-36-9-18 & #424-36-9-18  
SECTION 36, T9S, R18E, S.L.B.&M.  
SW 1/4 NE 1/4

**TOPOGRAPHIC** 08 29 12  
**MAP** MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: M.M. REVISED: 00-00-00







APPROXIMATE TOTAL PIPELINE DISTANCE = 303' +/-

# LEGEND:

- EXISTING ROAD
- - - - - PROPOSED ROAD
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



# GASCO PRODUCTION COMPANY

DESERT SPRINGS STATE #314-36-9-18,  
#412-36-9-18 & #424-36-9-18  
SECTION 36, T9S, R18E, S.L.B.&M.  
SW 1/4 NE 1/4

ACCESS ROAD  
MAP

08 29 12  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: M.M. REVISED: 00-00-00

**D**  
TOPO





## **Gasco Energy**

**Uintah County, UT**

**Sec 36, T9S, R18E - Desert Springs**

**Desert Springs State #412-36-9-18**

**Original Hole**

**Plan: Plan #1**

## **Standard Planning Report**

**09 November, 2012**

***gyro/data***

**Precision Wellbore Placement**



## Planning Report

**gyrodata**  
 Precision Wellbore Placement

<b>Database:</b>	Gyrodata Single User DB	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Company:</b>	Gasco Energy	<b>TVD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Site:</b>	Sec 36, T9S, R18E - Desert Springs	<b>North Reference:</b>	True
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	Plan #1		

<b>Project</b>	Uintah County, UT		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

Site		Sec 36, T9S, R18E - Desert Springs			
Site Position:		Northing:	605,545.93 usft	Latitude:	39° 59' 2.910 N
From:	Lat/Long	Easting:	2,462,998.31 usft	Longitude:	109° 50' 51.240 W
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence:	1.06 °

Well	Desert Springs State #412-36-9-18					
Well Position	+N-S	2,374.84 usft	Northing:	607,976.73 usft	Latitude:	39° 59' 26.380 N
	+E-W	3,051.64 usft	Easting:	2,466,005.55 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty	0.00 usft		Wellhead Elevation:		Ground Level:	4,912.00 usft

<b>Wellbore</b>	Original Hole				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2010	11/07/12	11.03	65.76	52,139

<b>Design</b>	Plan #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (usft)</b>	<b>+N-S (usft)</b>	<b>+E-W (usft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	35.57

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
600.00	6.00	35.57	599.45	12.77	9.13	2.00	2.00	0.00	35.57	
3,500.00	6.00	35.57	3,483.57	259.33	185.46	0.00	0.00	0.00	0.00	
4,142.92	25.29	35.57	4,099.75	399.69	285.83	3.00	3.00	0.00	0.00	
5,342.28	25.29	35.57	5,184.18	816.41	583.85	0.00	0.00	0.00	0.00	
6,185.20	0.00	0.00	6,000.00	965.27	690.31	3.00	-3.00	0.00	180.00	
12,885.20	0.00	0.00	12,700.00	965.27	690.31	0.00	0.00	0.00	0.00	PBHL (DSS #412-36-)





## Planning Report



Precision Wellbore Placement

<b>Database:</b>	Gyrodatab Single User DB	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Company:</b>	Gasco Energy	<b>TVD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Site:</b>	Sec 36, T9S, R18E - Desert Springs	<b>North Reference:</b>	True
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	Plan #1		

## Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/S (usft)	+E/W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
60.00	0.00	0.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>13 3/8"</b>									
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Start Build 2.00</b>									
400.00	2.00	35.57	399.98	1.42	1.02	1.75	2.00	2.00	0.00
500.00	4.00	35.57	499.84	5.68	4.06	6.98	2.00	2.00	0.00
600.00	6.00	35.57	599.45	12.77	9.13	15.69	2.00	2.00	0.00
<b>Start 2900.00 hold at 600.00 MD</b>									
700.00	6.00	35.57	698.90	21.27	15.21	26.15	0.00	0.00	0.00
800.00	6.00	35.57	798.36	29.77	21.29	36.60	0.00	0.00	0.00
900.00	6.00	35.57	897.81	38.27	27.37	47.05	0.00	0.00	0.00
1,000.00	6.00	35.57	997.26	46.77	33.45	57.50	0.00	0.00	0.00
1,100.00	6.00	35.57	1,096.71	55.28	39.53	67.96	0.00	0.00	0.00
1,200.00	6.00	35.57	1,196.17	63.78	45.61	78.41	0.00	0.00	0.00
1,300.00	6.00	35.57	1,295.62	72.28	51.69	88.86	0.00	0.00	0.00
1,400.00	6.00	35.57	1,395.07	80.78	57.77	99.32	0.00	0.00	0.00
1,500.00	6.00	35.57	1,494.52	89.29	63.85	109.77	0.00	0.00	0.00
1,600.00	6.00	35.57	1,593.97	97.79	69.93	120.22	0.00	0.00	0.00
1,700.00	6.00	35.57	1,693.43	106.29	76.01	130.67	0.00	0.00	0.00
1,800.00	6.00	35.57	1,792.88	114.79	82.09	141.13	0.00	0.00	0.00
1,900.00	6.00	35.57	1,892.33	123.30	88.17	151.58	0.00	0.00	0.00
2,000.00	6.00	35.57	1,991.78	131.80	94.25	162.03	0.00	0.00	0.00
2,100.00	6.00	35.57	2,091.23	140.30	100.33	172.49	0.00	0.00	0.00
2,200.00	6.00	35.57	2,190.69	148.80	106.42	182.94	0.00	0.00	0.00
2,300.00	6.00	35.57	2,290.14	157.31	112.50	193.39	0.00	0.00	0.00
2,400.00	6.00	35.57	2,389.59	165.81	118.58	203.84	0.00	0.00	0.00
2,500.00	6.00	35.57	2,489.04	174.31	124.66	214.30	0.00	0.00	0.00
2,600.00	6.00	35.57	2,588.50	182.81	130.74	224.75	0.00	0.00	0.00
2,700.00	6.00	35.57	2,687.95	191.32	136.82	235.20	0.00	0.00	0.00
2,800.00	6.00	35.57	2,787.40	199.82	142.90	245.66	0.00	0.00	0.00
2,900.00	6.00	35.57	2,886.85	208.32	148.98	256.11	0.00	0.00	0.00
3,000.00	6.00	35.57	2,986.30	216.82	155.06	266.56	0.00	0.00	0.00
3,100.00	6.00	35.57	3,085.76	225.33	161.14	277.01	0.00	0.00	0.00
3,200.00	6.00	35.57	3,185.21	233.83	167.22	287.47	0.00	0.00	0.00
3,300.00	6.00	35.57	3,284.66	242.33	173.30	297.92	0.00	0.00	0.00
3,400.00	6.00	35.57	3,384.11	250.83	179.38	308.37	0.00	0.00	0.00
<b>9 5/8"</b>									
3,500.00	6.00	35.57	3,483.57	259.33	185.46	318.83	0.00	0.00	0.00
<b>Start DLS 3.00 TFO 0.00</b>									
3,600.00	9.00	35.57	3,582.70	269.95	193.05	331.88	3.00	3.00	0.00
3,700.00	12.00	35.57	3,681.01	284.77	203.65	350.10	3.00	3.00	0.00
3,800.00	15.00	35.57	3,778.24	303.76	217.23	373.44	3.00	3.00	0.00
3,900.00	18.00	35.57	3,874.11	326.86	233.75	401.84	3.00	3.00	0.00
4,000.00	21.00	35.57	3,968.36	354.01	253.16	435.22	3.00	3.00	0.00
4,100.00	24.00	35.57	4,060.74	385.13	275.42	473.48	3.00	3.00	0.00
4,142.91	25.29	35.57	4,099.74	399.68	285.83	491.37	3.00	3.00	0.00
<b>Start 1199.38 hold at 4142.91 MD</b>									
4,142.92	25.29	35.57	4,099.75	399.69	285.83	491.37	3.00	3.00	0.00





## Planning Report



Precision Wellbore Placement

<b>Database:</b>	Gyrodata Single User DB	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Company:</b>	Gasco Energy	<b>TVD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Project:</b>	Utintah County, UT	<b>MD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Site:</b>	Sec 36, T9S, R18E - Desert Springs	<b>North Reference:</b>	True
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	Plan #1		

## Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/S (usft)	+E/W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,200.00	25.29	35.57	4,151.36	419.52	300.02	515.76	0.00	0.00	0.00
4,300.00	25.29	35.57	4,241.78	454.27	324.86	558.47	0.00	0.00	0.00
4,400.00	25.29	35.57	4,332.20	489.01	349.71	601.19	0.00	0.00	0.00
4,500.00	25.29	35.57	4,422.61	523.76	374.56	643.91	0.00	0.00	0.00
4,600.00	25.29	35.57	4,513.03	558.50	399.41	686.62	0.00	0.00	0.00
4,700.00	25.29	35.57	4,603.45	593.25	424.26	729.34	0.00	0.00	0.00
4,800.00	25.29	35.57	4,693.87	627.99	449.10	772.05	0.00	0.00	0.00
4,900.00	25.29	35.57	4,784.28	662.74	473.95	814.77	0.00	0.00	0.00
5,000.00	25.29	35.57	4,874.70	697.48	498.80	857.49	0.00	0.00	0.00
5,100.00	25.29	35.57	4,965.12	732.23	523.65	900.20	0.00	0.00	0.00
5,200.00	25.29	35.57	5,055.54	766.97	548.50	942.92	0.00	0.00	0.00
5,298.94	25.29	35.57	5,145.00	801.35	573.08	985.18	0.00	0.00	0.00
<b>Wasatch</b>									
5,300.00	25.29	35.57	5,145.95	801.72	573.34	985.63	0.00	0.00	0.00
5,342.29	25.29	35.57	5,184.19	816.41	583.85	1,003.70	0.00	0.00	0.00
<b>Start Drop -3.00</b>									
5,400.00	23.56	35.57	5,236.74	835.82	597.73	1,027.56	3.00	-3.00	0.00
5,500.00	20.56	35.57	5,329.41	866.36	619.57	1,065.10	3.00	-3.00	0.00
5,600.00	17.56	35.57	5,423.92	892.91	638.56	1,097.75	3.00	-3.00	0.00
5,700.00	14.56	35.57	5,520.01	915.41	654.65	1,125.40	3.00	-3.00	0.00
5,800.00	11.56	35.57	5,617.41	933.78	667.79	1,147.99	3.00	-3.00	0.00
5,900.00	8.56	35.57	5,715.86	947.98	677.94	1,165.45	3.00	-3.00	0.00
6,000.00	5.56	35.57	5,815.09	957.97	685.09	1,177.73	3.00	-3.00	0.00
6,100.00	2.56	35.57	5,914.83	963.72	689.20	1,184.81	3.00	-3.00	0.00
6,185.20	0.00	0.00	6,000.00	965.27	690.31	1,186.71	3.00	-3.00	-41.75
<b>Start 6700.00 hold at 6185.20 MD</b>									
6,200.00	0.00	0.00	6,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,300.00	0.00	0.00	6,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,400.00	0.00	0.00	6,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,500.00	0.00	0.00	6,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,600.00	0.00	0.00	6,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,700.00	0.00	0.00	6,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,800.00	0.00	0.00	6,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
6,900.00	0.00	0.00	6,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,000.00	0.00	0.00	6,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,100.00	0.00	0.00	6,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,200.00	0.00	0.00	7,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,300.00	0.00	0.00	7,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,400.00	0.00	0.00	7,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,500.00	0.00	0.00	7,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,600.00	0.00	0.00	7,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,700.00	0.00	0.00	7,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,800.00	0.00	0.00	7,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
7,900.00	0.00	0.00	7,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,000.00	0.00	0.00	7,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,100.00	0.00	0.00	7,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,200.00	0.00	0.00	8,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,300.00	0.00	0.00	8,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,400.00	0.00	0.00	8,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,500.00	0.00	0.00	8,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,600.00	0.00	0.00	8,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,700.00	0.00	0.00	8,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00





## Planning Report



<b>Database:</b>	Gyrodatab Single User DB	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Company:</b>	Gasco Energy	<b>TVD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	Est RKB=15' @ 4927.00usft (Original Well Elev)
<b>Site:</b>	Sec 36, T9S, R18E - Desert Springs	<b>North Reference:</b>	True
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	Plan #1		

## Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,800.00	0.00	0.00	8,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
8,900.00	0.00	0.00	8,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,000.00	0.00	0.00	8,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,100.00	0.00	0.00	8,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,200.00	0.00	0.00	9,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,220.20	0.00	0.00	9,035.00	965.27	690.31	1,186.71	0.00	0.00	0.00
<b>Mesaverde</b>									
9,300.00	0.00	0.00	9,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,400.00	0.00	0.00	9,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,500.00	0.00	0.00	9,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,600.00	0.00	0.00	9,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,700.00	0.00	0.00	9,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,800.00	0.00	0.00	9,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
9,900.00	0.00	0.00	9,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,000.00	0.00	0.00	9,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,100.00	0.00	0.00	9,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,200.00	0.00	0.00	10,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,300.00	0.00	0.00	10,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,400.00	0.00	0.00	10,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,500.00	0.00	0.00	10,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,600.00	0.00	0.00	10,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,700.00	0.00	0.00	10,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,800.00	0.00	0.00	10,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
10,900.00	0.00	0.00	10,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,000.00	0.00	0.00	10,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,100.00	0.00	0.00	10,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,200.00	0.00	0.00	11,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,300.00	0.00	0.00	11,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,400.00	0.00	0.00	11,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,500.00	0.00	0.00	11,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,600.00	0.00	0.00	11,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,640.20	0.00	0.00	11,455.00	965.27	690.31	1,186.71	0.00	0.00	0.00
<b>Castlegate</b>									
11,700.00	0.00	0.00	11,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,800.00	0.00	0.00	11,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,900.00	0.00	0.00	11,714.80	965.27	690.31	1,186.71	0.00	0.00	0.00
11,920.20	0.00	0.00	11,735.00	965.27	690.31	1,186.71	0.00	0.00	0.00
<b>Blackhawk</b>									
12,000.00	0.00	0.00	11,814.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,100.00	0.00	0.00	11,914.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,200.00	0.00	0.00	12,014.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,300.00	0.00	0.00	12,114.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,400.00	0.00	0.00	12,214.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,500.00	0.00	0.00	12,314.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,550.20	0.00	0.00	12,365.00	965.27	690.31	1,186.71	0.00	0.00	0.00
<b>Spring Canyon</b>									
12,600.00	0.00	0.00	12,414.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,700.00	0.00	0.00	12,514.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,800.00	0.00	0.00	12,614.80	965.27	690.31	1,186.71	0.00	0.00	0.00
12,885.20	0.00	0.00	12,700.00	965.27	690.31	1,186.71	0.00	0.00	0.00
<b>TD at 12885.20 - PBHL (DSS #412-36-9-18)</b>									





## Planning Report

**gyro/data**

Precision Wellbore Placement

**Database:** Gyrodata Single User DB  
**Company:** Gasco Energy  
**Project:** Uintah County, UT  
**Site:** Sec 36, T9S, R18E - Desert Springs  
**Well:** Desert Springs State #412-36-9-18  
**Wellbore:** Original Hole  
**Design:** Plan #1

## Local Co-ordinate Reference:

## TVD Reference:

## MD Reference:

## North Reference:

## Survey Calculation Method:

Well Desert Springs State #412-36-9-18  
 Est RKB=15' @ 4927.00usft (Original Well Elev)  
 Est RKB=15' @ 4927.00usft (Original Well Elev)  
 True  
 Minimum Curvature

## Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL (DSS #412-36-9-1 - plan hits target center - Point	0.00	0.00	12,700.00	965.27	690.31	608,954.67	2,466,677.79	39° 59' 35.920 N	109° 50' 3.160 W

## Casing Points

Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
60.00	60.00	13 3/8"	13-3/8	17-1/2
3,400.00	3,384.11	9 5/8"	9-5/8	12-1/4
12,885.20	12,700.00	4 1/2"	4-1/2	8-3/4

## Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
5,298.94	5,145.00	Wasatch		0.00	
9,220.20	9,035.00	Mesaverde		0.00	
11,640.20	11,455.00	Castlegate		0.00	
11,920.20	11,735.00	Blackhawk		0.00	
12,550.20	12,365.00	Spring Canyon		0.00	
12,885.20	12,700.00	TD		0.00	

## Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
300.00	300.00	0.00	0.00	Start Build 2.00
600.00	599.45	12.77	9.13	Start 2900.00 hold at 600.00 MD
3,500.00	3,483.57	259.33	185.46	Start DLS 3.00 TFO 0.00
4,142.91	4,099.74	399.68	285.83	Start 1199.38 hold at 4142.91 MD
5,342.29	5,184.19	816.41	583.85	Start Drop -3.00
6,185.20	6,000.00	965.27	690.31	Start 6700.00 hold at 6185.20 MD
12,885.20	12,700.00	965.27	690.31	TD at 12885.20






Company: Gasco Energy  
Field: Uintah County, UT  
Location: Sec 36, T9S, R18E - Desert Springs  
Well: Desert Springs State #412-36-9-18  
Original Hole

Plan: Plan #1 (Desert Springs State #412-36-9-18/Original Hole)  
Est RKB=15' @ 4927.00usft (Original Well Elev)

**gyrodata**

Precision Wellbore Placement



#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	
3	600.00	6.00	35.57	599.45	12.77	9.13	2.00	35.57	15.69	
4	3500.00	6.00	35.57	3483.57	259.33	185.46	0.00	0.00	318.83	
5	4142.91	25.29	35.57	4099.75	399.69	285.83	3.00	0.00	491.37	
6	5342.28	25.29	35.57	5184.18	816.41	583.85	0.00	0.00	1003.70	
7	6185.20	0.00	0.00	6000.00	965.27	690.31	3.00	180.00	1186.71	
8	12885.20	0.00	0.00	12700.00	965.27	690.31	0.00	0.00	1186.71	PBHL (DSS #412-36-9-18)

#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Shape
PBHL (DSS #412-36-9-18)	12700.00	965.27	690.31	608954.67	2466677.80	Point

#### WELL DETAILS: Desert Springs State #412-36-9-18

Ground Elev: 4912.00					
Est RKB=15' @ 4927.00usft (Original Well Elev)					
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	607976.73	2466005.56	39° 59' 26.380 N	109° 50' 12.030 W

#### ANNOTATIONS

TVD	MD	Annotation
300.00	300.00	Start Build 2.00
599.45	600.00	Start 2900.00 hold at 600.00 MD
3483.57	3500.00	Start DLS 3.00 TFO 0.00
4099.74	4142.91	Start 1199.38 hold at 4142.91 MD
5184.19	5342.29	Start Drop -3.00
6000.00	6185.20	Start 6700.00 hold at 6185.20 MD
12700.00	12885.20	TD at 12885.20

#### FORMATION TOPS ALONG WELLPATH



TVDPath	MDPath	Formation
5145.00	5298.94	Wasatch
9035.00	9220.20	Mesaverde
11455.00	11640.20	Castlegate
11735.00	11920.20	Blackhawk
12365.00	12550.20	Spring Canyon
12700.00	12885.20	TD

#### CASING DETAILS

TVD	MD	Name	Size
60.00	60.00	13 3/8"	13-3/8
3384.11	3400.00	9 5/8"	9-5/8
12700.00	12885.20	4 1/2"	4-1/2

Plan: Plan #1 (Desert Springs State #412-36-9-18/Original Hole)

Created By: M. Routh Date: 8:20, November 09 2012





**Gasco Production Company**  
Desert Springs State 412-36-9-18  
NE/NE, Section 36, Township 9 South, Range 18 East  
Uintah County, Utah  
Lease No. ML-45171

ONSHORE OIL & GAS ORDER NO. 1

**Notification Requirements**

Location Construction-	48 hours prior to construction of location and access roads
Location completion-	prior to moving on with drilling rig.
Spud Notice-	at least 24 hours prior to spudding the well.
Casing String and Cementing-	24 hours notice prior to running casing and cementing.
BOP and Related Equipment-	24 hours prior to initiating pressure tests.
First Production Notice-	Within 5 business days after new well begins or production resumes after well has been off production for more than 90 days.

The onsite inspection for the subject well site will be conducted with at least one of the land management agency specialists and Gasco which may include the following individuals:

UDOGM Representative  
SITLA Representative  
Gasco Production Company  
Uintah Engineer and Land Surveying

**1. Existing Roads**

See Attached Topographic Map "A".

Description of travel from plats.

**2. Planned Access Road**

See Attached Topographic Map "B" for location of the proposed access road.

**3. Location of Existing Wells**

See Attached Topographic Map "C"

**4. Location of Tank Batteries and Production Facilities**

- a. All permanent surface equipment will be painted a Color approved by the land management agency.
- b. Storage tanks batteries will be surrounded by containment dike of sufficient capacity to contain at a minimum, the entire contents of the largest tank with in the contained area, unless more stringent requirements are necessary as notified by the AO.
- c. A production layout will be submitted via sundry upon proven productivity of the well.
- d. All loading lines will be placed inside the berm/dike surrounding the tank battery.
- e. A Gas Meter Run will be placed within 500 ft. of the wellhead. Meter runs will be housed. The oil and gas measurement equipment will be installed on the well location. Measurement equipment will be calibrated in place prior to any deliveries. Tests for accuracy will be conducted monthly for the first three months on new installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the calibration reports will be submitted to the Vernal Field Office.
- f. Any necessary pits will be properly fenced to prevent any wildlife entry.
- g. The access road will be maintained in a safe, usable condition conducive to the climate and seasonal conditions in order to accommodate daily operation of the well and prevent erosion.
- h. Pipelines, up to 6" steel, will follow the proposed access for approximately 303', as detailed in attached Map "D". The pipeline will be laid on the surface except road crossings where they will be buried to a depth of 3'-5'. The method of coupling will be welded. Associated pipeline components, such as risers, pig launchers/catchers, meters, valves, etc. will be contained within the 30' needed for construction of the pipeline. This pipeline will service all the wells located on this pad.

**5. Location and Type of Water**

- a. Water will come from: Water Right No. 41-3530.
- b. Water will be hauled by commercial transport over the access roads shown on Attached Maps "A" and "B".
- c. No water well will be drilled on this lease.



**6. Source of Construction Material**

- a. Any gravel used will be obtained from a commercial source.
- b. The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2.3.
- c. No construction materials will be used from Federal lands.

**7. Methods of Handling Waste Disposal**

- a. the reserve pit will be double lined with at least 16 mil liners.
- b. All trash will be contained in an enclosed trash container through the drilling, completion, and facility construction phases and its contents removed and hauled to an approved disposal sight as needed.
- c. A chemical porta-toilet will be furnished through the drilling, and completion phases.
- d. After first production, produced waste water will be confined to an unlined pit or storage tank for a period not to exceed 90 days. During the 90 day period, in accordance with Onshore Order No. 7, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted for the AO's approval.
- e. Drill cuttings are to be contained and buried in the reserve pit.
- f. Any salts and/or chemicals which are an integral part of the drilling system will be disposed of in the same manner as the drilling fluid.

**8. Ancillary Facilities**

There are no airstrips, camps or other facilities planned during the drilling of this well except for those facilities needed for drilling rig personal, service providers and company representatives.

**9. Well Site Layout**

See attached Location Layout Diagram

**10. Plans for Restoration of Surface**

- a. Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Upon completion, any hydrocarbon within the reserve pit will be removed in accordance with 43 CFR 3162.7-1.
- c. The reserve pit will be backfilled and reclaimed within 120 days from the well completion. The reserve pit liner will be perforated and excess liner removed before backfilling. Alternatively, the pit will be pumped dry, the liner folded into the pit and buried to a minimum of 4' deep.

d. That portion of the location not needed for production facilities or operations, or any disturbed areas upon final plug and abandonment, will be re-contoured to approximate natural contours and seeded with a seed mixture and procedure specified by the AO. Additionally, the topsoil pile will be seeded with the same mixture and procedure as specified.

#### **11. Surface Ownership**

The proposed access road and well pad is on lands managed by the State of Utah.

#### **12. Other Information**

a. An archeological and Paleontological survey was conducted. They will be submitted under a separate cover.

b. If historic or archeological materials are uncovered during construction, the operator will immediately stop work and contact the AO.

c. COA's from onsite will be implemented/followed.

d. The operator will control noxious weeds along associated well pad, roads, pipelines, and surface equipment. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted and approved prior to the application of pesticides or herbicides.

e. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal lands after the conclusion of drilling operations or at any other time without BLM authorization.

f. All lease and unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notices to Lessees. The operator is fully responsible for the actions of his subcontractors.

g. A complete copy of the APD shall be on location during construction and drilling of this site.

#### **Water Disposal**

Immediately upon first production all produced water will be confined to a steel storage tank. Water will be disposed of via truck transport to a State of Utah approved disposal site.



**Wildlife Timing Stipulations** COA's from onsite will be implemented/followed.

**13. Lessee's or Operators Representative**

**Gasco Production Company**

Roger Knight – EHS Supervisor  
7979 East Tufts Avenue, Suite 1150  
Denver, CO 80237  
(303) 996-1803 – office  
(720) 810-3850 – cell

Jesse Duncan

PO Box 351  
10569 Pariette Road  
Myton, Utah 84052  
(435)828-1221 - Cell  
(435)636-3336 – office

**Certification**

Please be advised that *Gasco Production Company* is considered to be the operator of the *Well Desert Springs State 412-36-9-18 , NE/NE Section 36, T9S, R18E, Lease No. ML-45171, Uintah County, Utah*; and is responsible under the term and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond K08792707.

I hereby certify that the proposed drill site and access road have been inspected and I am familiar with the conditions that currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Gasco Production Company its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. The statement is subject to the provisions of 18 U.S.C. 1000 for the filing of a false statement.




Roger Knight  
EHS Supervisor  
Gasco Production Company

2-20-13

Date

EXHIBIT "F"



BOP Equipment  
5000psi WP



November 19, 2012

**Gasco Production Company**  
Desert Springs State 412-36-9-18  
495' FNL & 660' FEL  
NENE of Section 36-T9S-R18E  
Uintah County, UT

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the well site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

  
\_\_\_\_\_  
Signature

Senior Operations Manager  
\_\_\_\_\_  
Title

7979 East Tufts Avenue, Suite 1150 Denver, CO 80237  
\_\_\_\_\_  
Address

303-483-0044  
\_\_\_\_\_  
Phone

trogers@gascoenergy.com  
\_\_\_\_\_  
E-mail






1" = 40'  
X-Section  
Scale  
1" = 100'

DATE: 08-29-12  
DRAWN BY: T.B.

# **GASCO PRODUCTION COMPANY**

**TYPICAL CROSS SECTIONS FOR**  
**DESERT SPRINGS STATE #314-36-9-18,**  
**#412-36-9-18 & #424-36-9-18**  
**SECTION 36, T9S, R18E, S.L.B.&M.**  
**SW 1/4 NE 1/4**

**FIGURE #2**



## **NOTE:**

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

## **APPROXIMATE ACREAGES**

WELL SITE DISTURBANCE = ± 3.742 ACRES  
ACCESS ROAD DISTURBANCE = ± 0.189 ACRES  
PIPELINE DISTURBANCE = ± 0.209 ACRES  
TOTAL = ± 4.140 ACRES

## **\* NOTE:**

FILL QUANTITY INCLUDES 5% FOR COMPACTION

## **APPROXIMATE YARDAGES**


(6") Topsoil Stripping = 2,550 Cu. Yds.  
Remaining Location = 12,210 Cu. Yds.  
**TOTAL CUT = 14,760 CU. YDS.**  
**FILL = 6,990 CU. YDS.**

EXCESS MATERIAL = 7,770 Cu. Yds.  
Topsoil & Pit Backfill = 7,770 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 0 Cu. Yds.  
(After Interim Rehabilitation)

**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017









**API Number: 4304753324**  
**Well Name: Desert Springs State 412-36-9-18**  
**Township T09.0S Range R18.0E Section 36**  
**Meridian: SLBM**  
**Operator: GASCO PRODUCTION COMPANY**  
Map Prepared:  
Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
Fields	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dls
STORAGE	
TERMINATED	





December 5, 2012

State of Utah Division Oil, Gas and Mining  
PO Box 145801  
Salt Lake City, UT 84114-5801

**RE: Exception Location Request  
Desert Springs State 412-36-9-18  
1462 FNL, 1352 FEL (surface) 495 FNL, 660 FEL (bottomhole)  
Township 9 South, Range 18 East, SLM  
Section 36: NE $\frac{1}{4}$ NE $\frac{1}{4}$   
Uintah County, Utah**

To Whom It May Concern:

Pursuant to Rule 649-3-11 of UDOGM Rules and Regulations, Gasco Production Company ("Gasco") requests an exception to this location. The DSS 412-36-9-18 will be directionally drilled to minimize surface disturbance and impacts by using one surface location for multiple wells. Additionally Gasco is the owner of the oil and gas lease and the sole working interest owner within the 460' for the entire directional well bore.

Sincerely,

A handwritten signature in blue ink, appearing to read "R. Knight", is written over a large, diagonal, red "CONFIDENTIAL" watermark.

Roger Knight  
EHS Supervisor

Gasco Production Company  
7979 East Tufts Avenue, Suite 1150  
Denver, CO 80237

Tel: (303) 483-0044  
Fax (303) 483-0011  
Email: rknight@gascoenergy.com





Mail

Inbox (24)

Starred

Important

Sent Mail

Drafts (2)

BLM (54)

Cabinet

Electronic filing

Eng. Tech

Follow up

Misc

Priority

Tariq

More

ESPN.com - [Mavericks owner says 'Bank of Cuban' is open](#) - 8 hours ago

Web Clip

## Gasco Approvals

Inbox x



**Jeff Conley**

Jan 11 (4 days ago) ★

to me, Brad, rknight, Jim, Lavonne

Hello,

The following wells have been cleared for both arch and paleo by SITLA:

Gasco's Desert Springs State 424-36-9-18 [API #[4304753325](#)] (U-12-MQ-1039s)

Gasco's Desert Springs State 412-36-9-18 [API #[4304753324](#)] (U-12-MQ-1039s)

Gasco's Desert Springs State 314-36-9-18 [API #[4304753328](#)] (U-12-MQ-1039s)

Thank you,

Jeff Conley  
SITLA Resource Specialist  
[jconley@utah.gov](mailto:jconley@utah.gov)  
[801-538-5157](tel:801-538-5157)  
Reply Forward



Click here to [Reply](#), [Reply to all](#), or [Forward](#)

dianawhitney@utah.gov

14 of 77

More

People (5)

**Jeff Conley**

TRUST LANDS RESOURCE SP...

[Show details](#)

CONFIDENTIAL

Well Name	GASCO PRODUCTION COMPANY Desert Springs State 412-36-9-18			
String	COND	SURF	PROD	
Casing Size(")	13.375	9.625	4.500	
Setting Depth (TVD)	60	3400	12700	
Previous Shoe Setting Depth (TVD)	0	60	3400	
Max Mud Weight (ppg)	8.3	8.3	11.6	
BOPE Proposed (psi)	0	1000	5000	
Casing Internal Yield (psi)	1000	3520	12410	
Operators Max Anticipated Pressure (psi)	7655		11.6	

Calculations	COND String	13.375	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO <input type="text" value="air/mist system"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO <input type="text" value=""/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO <input type="text" value=""/>
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient

Calculations	SURF String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	1467	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	1059	NO <input type="text" value="air/mist system"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	719	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	732	NO <input type="text" value="OK"/>
Required Casing/BOPE Test Pressure=		2464	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient


Calculations	PROD String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	7661	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	6137	NO <input type="text" value="WBM"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4867	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	5615	NO <input type="text" value="OK"/>
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		3400	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="text" value=""/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="text" value=""/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="text" value=""/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient



# 43047533240000 Desert Springs State 412-36-9-18

## Casing Schematic



Well name:	<b>43047533240000 Desert Springs State 412-36-9-18</b>	
Operator:	<b>GASCO PRODUCTION COMPANY</b>	
String type:	Surface	Project ID: 43-047-53324
Location:	UINTAH COUNTY	

**Design parameters:****Collapse**

Mud weight: 8.300 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 121 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: 866 ft

**Burst**

Max anticipated surface pressure: 2,978 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 3,384 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.  
Neutral point: 2,982 ft

**Directional well information:**

Kick-off point 300 ft  
Departure at shoe: 308 ft  
Maximum dogleg: 2 °/100ft  
Inclination at shoe: 6 °

**Re subsequent strings:**

Next setting depth: 12,700 ft  
Next mud weight: 11.600 ppg  
Next setting BHP: 7,653 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 3,384 ft  
Injection pressure: 3,384 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	3400	9.625	36.00	J-55	LT&C	3384	3400	8.796	27802
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	1459	2020	1.384	3384	3520	1.04	106.9	453	4.24 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 14, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 3384 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a



Well name:	<b>43047533240000 Desert Springs State 412-36-9-18</b>	
Operator:	<b>GASCO PRODUCTION COMPANY</b>	
String type:	Production	Project ID: 43-047-53324
Location:	UINTAH COUNTY	

**Design parameters:****Collapse**

Mud weight: 11.600 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 252 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 2,544 ft

**Burst**

Max anticipated surface pressure: 4,859 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 7,653 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 10,711 ft

**Directional Info - Build & Hold**

Kick-off point 300 ft  
Departure at shoe: 1187 ft  
Maximum dogleg: 3 °/100ft  
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	12885	4.5	13.50	HCP-110	LT&C	12700	12885	3.795	72200
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	7653	10680	1.396	7653	12410	1.62	171.4	338	1.97 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 14, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 12700 ft, a mud weight of 11.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** GASCO PRODUCTION COMPANY  
**Well Name** Desert Springs State 412-36-9-18  
**API Number** 43047533240000 **APD No** 7158 **Field/Unit** 8 MILE FLAT NORTH  
**Location: 1/4,1/4** SWNE **Sec** 36 **Tw** 9.0S **Rng** 18.0E 1462 FNL 1352 FEL  
**GPS Coord (UTM)** 599253 4427364 **Surface Owner**

### **Participants**

Sam LaRue (environmental consultant), McCoy Anderson (surveyor), Jesse Duncan (Gasco), Jeff Conley (SITLA)

### **Regional/Local Setting & Topography**

This proposed well sits to the east of the Monarch Desert Springs water disposal ponds, and just over a mile west of the Green River. Myton, UT is approximately 25 miles to the north west. The proposed site slopes gently north away from a large draw which lies to the south of the location.

### **Surface Use Plan**

**Current Surface Use**  
Grazing

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0.05	<b>Width</b> 220 <b>Length</b> 410	Onsite	UNTA

**Ancillary Facilities** N

**Waste Management Plan Adequate?** Y

### **Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

Prickly pear, grasses, small sage, spiny hopsage

**Soil Type and Characteristics**

clay loam soil with fractured shale scattered on surface

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required?** N

**Berm Required?** N

**Erosion Sedimentation Control Required?** N



Paleo Survey Run? Y    Paleo Potential Observed? N    Cultural Survey Run? Y    Cultural Resources? N

### Reserve Pit

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	100 to 200	5
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	Mod permeability	10
Fluid Type	TDS>5000 and	10
Drill Cuttings	Salt or Detrimental	10
Annual Precipitation (inches)		0
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
<b>Final Score</b>		55    1 Sensitivity Level

### Characteristics / Requirements

The proposed reserve pit dimensions are 240ft x 13ft x 12ft deep. A 20 mil liner will be required because the pit will be used for 3 wells. The reserve pit is proposed in a cut stable location.

Closed Loop Mud Required? N    Liner Required? Y    Liner Thickness 20    Pit Underlayment Required? Y

### Other Observations / Comments

This is a 3 well pad occupied by 43-047-53324, 53328, and 53325

Richard Powell  
Evaluator

12/5/2012  
Date / Time

# Application for Permit to Drill Statement of Basis Utah Division of Oil, Gas and Mining

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
7158	43047533240000	LOCKED	GW	S	No
<b>Operator</b>	GASCO PRODUCTION COMPANY		<b>Surface Owner-APD</b>		
<b>Well Name</b>	Desert Springs State 412-36-9-18		<b>Unit</b>		
<b>Field</b>	8 MILE FLAT NORTH		<b>Type of Work</b>	DRILL	
<b>Location</b>	SWNE 36 9S 18E S 1462 FNL 1352 FEL GPS Coord (UTM) 599283E 4427359N				

## Geologic Statement of Basis

Gasco proposes to set 60' of conductor and 3,400' of surface casing at this location. Conductor and surface holes will be drilled with an air mist system and both will be cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,500'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 36. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement programs should adequately protect ground water in this area.

Brad Hill  
**APD Evaluator**

12/18/2012  
**Date / Time**

## Surface Statement of Basis

This proposed well is on SITLA surface with SITLA minerals. SITLA representative Jeff Conley was present for the onsite and stated that he has no concerns with this site. DWR representative Ben Williams was invited but unable to attend the onsite. Mr. Williams stated that this is year long pronghorn habitat but made no recommendations regarding this site. This is a flat stable location and appears to be a good site for placement of this well. A 20 mil liner was agreed to based on the fact that 3 wells will be drilled here and the pit will be subject to a longer use period than a single well pad. There do not appear to be any drainage diversions needed for this well site.

Richard Powell  
**Onsite Evaluator**

12/5/2012  
**Date / Time**

## Conditions of Approval / Application for Permit to Drill

<b>Category</b>	<b>Condition</b>
Pits	A synthetic liner with a minimum thickness of 20 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.



## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/19/2012

API NO. ASSIGNED: 43047533240000

WELL NAME: Desert Springs State 412-36-9-18

OPERATOR: GASCO PRODUCTION COMPANY (N2575)

PHONE NUMBER: 303 996-1803

CONTACT: Roger Knight

PROPOSED LOCATION: SWNE 36 090S 180E

Permit Tech Review: ☒

SURFACE: 1462 FNL 1352 FEL

Engineering Review: ☒

BOTTOM: 0495 FNL 0660 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 39.99058

LONGITUDE: -109.83706

UTM SURF EASTINGS: 599283.00

NORTHINGS: 4427359.00

FIELD NAME: 8 MILE FLAT NORTH

LEASE TYPE: 3 - State

LEASE NUMBER: ML45171

PROPOSED PRODUCING FORMATION(S): MESA VERDE

SURFACE OWNER: 3 - State

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE/FEE - K08792707☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 41-3530☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-11

Effective Date:

Siting:

☒ R649-3-11. Directional Drill

Comments: Presite Completed

## Stipulations:

- 1 - Exception Location - bhill
- 5 - Statement of Basis - bhill
- 12 - Cement Volume (3) - ddoucet
- 15 - Directional - dmason
- 23 - Spacing - dmason
- 25 - Surface Casing - hmacdonald

RECEIVED: March 12, 2013



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** Desert Springs State 412-36-9-18  
**API Well Number:** 43047533240000  
**Lease Number:** ML45171  
**Surface Owner:** STATE  
**Approval Date:** 3/12/2013

### Issued to:

GASCO PRODUCTION COMPANY, 8 Inverness Dr. East, Suite 100, Englewood, CO 80112

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-11. The expected producing formation or pool is the MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon



as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 4 1/2 production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to a minimum of 3000'.

Surface casing shall be cemented to the surface.

**Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website  
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program  
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

**Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-231-8956 - after office hours

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining,

including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 1/1/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION         </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco proposes the following changes to the approved casing program: Surface Casing Hole size: 11.0" Csg size: 8.625" Length: 0-3400' Weight: 32# Grade & thread: J-55 LT&C Max Mud Weight: 8.3 Production Casing Hole Size: 7.875" Csg Size: 4.5" Length: 0-12893' Weight: 13.5# Grade & thread: HCP-110 LT&C Max Mud Weight: 11.6		
<b>Approved by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b>  <b>Date:</b> December 11, 2013 <b>By:</b> <u>Derek Duff</u>		
<b>NAME (PLEASE PRINT)</b> Jessica Berg		<b>PHONE NUMBER</b> 303 996-1805
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst
<b>DATE</b> 11/26/2013		

Well name:	<b>43047533240000 Desert Springs State 412-36-9-18</b>	
Operator:	<b>GASCO PRODUCTION COMPANY</b>	
String type:	Surface	Project ID: 43-047-53324
Location:	UINTAH COUNTY	

**Design parameters:****Collapse**

Mud weight: 8.300 ppg  
Design is based on evacuated pipe.

**Burst**

Max anticipated surface pressure: 2,978 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP: 3,384 psi

No backup mud specified.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.  
Neutral point: 2,981 ft

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 121 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: 270 ft @ 12% w/o  
to surf @ 9% w/o, fail 2956'

**Directional well information:**

Kick-off point: 300 ft  
Departure at shoe: 308 ft  
Maximum dogleg: 2 °/100ft  
Inclination at shoe: 6 °

**Re subsequent strings:**

Next setting depth: 12,708 ft  
Next mud weight: 11.600 ppg  
Next setting BHP: 7,658 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 3,384 ft  
Injection pressure: 3,384 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	3400	8.625	32.00	J-55	LT&C	3384	3400	7.875	27399

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	1459	2530	1.734	3384	3930	1.16	94.9	417	4.39 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: December 10, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 3384 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	<b>43047533240000 Desert Springs State 412-36-9-18</b>	
Operator:	<b>GASCO PRODUCTION COMPANY</b>	
String type:	Production	Project ID: 43-047-53324
Location:	UINTAH COUNTY	

**Design parameters:****Collapse**

Mud weight: 11.600 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 252 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 4,862 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 7,658 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Directional well information:**

Kick-off point 300 ft  
Departure at shoe: 1187 ft  
Maximum dogleg: 3 °/100ft  
Inclination at shoe: 0 °

Tension is based on air weight.  
Neutral point: 10,717 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	12893	4.5	13.50	HCP-110	LT&C	12708	12893	3.795	72245

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	7658	10680	1.395	7658	12410	1.62	171.6	338	1.97 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: December 10, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 12708 ft, a mud weight of 11.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

*Engineering responsibility for use of this design will be that of the purchaser.*



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 5/1/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input checked="" type="checkbox"/> <b>APD EXTENSION</b>          OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: March 13, 2014</p> <p style="color: red; font-weight: bold;">By: </p>		
<b>NAME (PLEASE PRINT)</b> Jessica Berg		<b>PHONE NUMBER</b> 303 996-1805
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst
<b>DATE</b> 3/13/2014		



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Request for Permit Extension Validation Well Number 43047533240000**

**API:** 43047533240000

**Well Name:** Desert Springs State 412-36-9-18

**Location:** 1462 FNL 1352 FEL QTR SWNE SEC 36 TWNP 090S RNG 180E MER S

**Company Permit Issued to:** GASCO PRODUCTION COMPANY

**Date Original Permit Issued:** 3/12/2013

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Signature:** Jessica Berg

**Date:** 3/13/2014

**Title:** Regulatory Analyst **Representing:** GASCO PRODUCTION COMPANY

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>4/7/2014</b>	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"><input type="checkbox"/> ACIDIZE</div> <div style="width: 33%;"><input type="checkbox"/> ALTER CASING</div> <div style="width: 33%;"><input type="checkbox"/> CASING REPAIR</div> <div style="width: 33%;"><input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TUBING</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL NAME</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL STATUS</div> <div style="width: 33%;"><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div style="width: 33%;"><input type="checkbox"/> CONVERT WELL TYPE</div> <div style="width: 33%;"><input type="checkbox"/> DEEPEN</div> <div style="width: 33%;"><input type="checkbox"/> FRACTURE TREAT</div> <div style="width: 33%;"><input type="checkbox"/> NEW CONSTRUCTION</div> <div style="width: 33%;"><input type="checkbox"/> OPERATOR CHANGE</div> <div style="width: 33%;"><input type="checkbox"/> PLUG AND ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> PLUG BACK</div> <div style="width: 33%;"><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div style="width: 33%;"><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div style="width: 33%;"><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div style="width: 33%;"><input type="checkbox"/> TEMPORARY ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> TUBING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> VENT OR FLARE</div> <div style="width: 33%;"><input type="checkbox"/> WATER DISPOSAL</div> <div style="width: 33%;"><input type="checkbox"/> WATER SHUTOFF</div> <div style="width: 33%;"><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div style="width: 33%;"><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div style="width: 33%;"><input type="checkbox"/> OTHER</div> </div>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	
OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco proposes the following change to the drilling fluids program-  
 Conductor and surface csg are to be drilled with a mud and water  
 system, not an air myst system as stated in the APD.

**Approved by the  
 Utah Division of  
 Oil, Gas and Mining**

**Date:** April 07, 2014

**By:**

*[Signature]*

<b>NAME (PLEASE PRINT)</b> Jessica Berg	<b>PHONE NUMBER</b> 303 996-1805	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/4/2014	



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 4/14/2014	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Drilled 60' and set conductor.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> April 15, 2014		
<b>NAME (PLEASE PRINT)</b> Lindsey J. Cooke	<b>PHONE NUMBER</b> 303 996-1834	<b>TITLE</b> Production Tech
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/15/2014	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/11/2014	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input checked="" type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input checked="" type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Gasco notified Dave Hackford at UDOGM of decision to plug back well on 7/10/14 at 9:30PM. Plug back took place 7/11/14. Plug #1 was set from 5733'-5133' with 195 sx of Class G Cement. Plug #2 was set from 3802' - 3502' with 128 sx of Class G Cement. Cement was tagged for a PBTD of 3508'. Gasco kicked off and is drilling around the old wellbore. See attached drilling report for additional details.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> July 14, 2014		
<b>NAME (PLEASE PRINT)</b> Jessica Berg	<b>PHONE NUMBER</b> 303 996-1805	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/14/2014	

## DAILY DRILLING REPORT

[illegible]



## DAILY DRILLING REPORT

[illegible]

## DAILY DRILLING REPORT

### TRIP OUT OF HOLE WITH OVERSHOT

## MUD REPORT

## BIT REPORT

**BIT CONDITION**

## PUMP REPORT

BHA TOTAL LENGTH	100
------------------	-----

4th RUN

.....

CASING RECORD			TOTAL DRILL GAS		TOUR CHECK			DEVIATION RECORD			KILL RATE @ 9,869'	
	DEPTH		GAS	UNITS	DEPTH		FL.	DEPTH	INC	AZ	PUMP 1	PUMP 2
SIZE	PROPOSED	ACTUAL	BGG	100	PICK UP		N/A	FISHING			SPM/PSI	SPM/PSI
8 5/8	3,000'	3006 GL	PEAK GAS	325	SLACK OFF		N/A				40/245	40/250
4 1/2	12,698'		CG	N/A	ROTATING		N/A				60/465	60/470
			TG	325	TORQUE		N/A				CO-MAN PHONE NO.	
FUEL USED	656	GALS	FLARE SCF's	0							435-828-0601	

## DAILY DRILLING REPORT



## DAILY DRILLING REPORT

Days from Spud <b>24</b>		Lease and Well No. <b>Desert Spring State 412-36-9-18</b>			Prospect/Field <b>8 Mile Flat North</b>			Date <b>11 Jul 2014</b>								
MD <b>10,152'</b>		TVD <b>9,976'</b>		Progress <b>0'</b>		Planned TD <b>12,698'</b>		Daily Cost <b>\$110,100</b>		Cumulative Cost <b>\$1,790,731</b>		AFE DHC \$ 1,275,900		AFE CWC \$ 2,802,700		
County <b>UINTAH</b>		API <b>43-047-53324</b>		State <b>UT</b>		Rig <b>SST RIG 54</b>		Drilling Supervisor <b>JERRY BARNES</b>		AFE Days (CWC) <b>18 Days</b>						
Present Operation <b>TRIPPING IN HOLE TO SIDE TRACK AFTER PLUG BACK</b>										AFE No. <b>14004</b>						
Time Log		OPERATIONS DESCRIPTION														
From	To	Hrs.														
6:00	9:00	3	TRIP OUT OF HOLE WITH OVERSHOT / NO RECOVERY / BREAK DOWN TOOLS AND LOAD OUT													
9:00	13:00	4	WAIT ON TOOLS TO RUN TUBING													
13:00	15:30	2.5	PJSM, RIG UP FRANKS TUBING TONGS AND PICK UP TUBING / RIG DOWN TONGS													
15:30	17:30	2	TRIP IN TUBING WITH DRILL PIPE TO SET PLUG BACK # 1 @ 5,733'													
17:30	19:00	1.5	CIRCULATE HOLE FOR CEMENT													
19:00			PJSM, RIG UP BAKER HUGHES CEMENTERS / PUMP PLUG # 1 - 5,733' TO 5,133' / 195 SX OF CLASS G CEMENT WITH 0.2% R-3, .002 GPS FP-6L / MIXED CEMENT AT 15.8 PPG WITH YIELD OF 1.15 CF/SX / DISPLACED WITH 1 BBL WATER & 65 BBL 9.6# MUD FOR A													
	20:00	1	BALANCED PLUG													
20:00	22:00	2	TRIP OUT 12 STANDS DRILL PIPE / CIRCULATED BOTTOMS UP / TRIP OUT TO 3,802' / CIRCULATE TO EVEN OUT MUD WEIGHT													
22:00			PJSM, PUMP PLUG # 2 - 3,802' TO 3,502' / 128 SX OF CLASS G CEMENT WITH 0.2% CD-32, 0.3% FL-63, 0.1% R-3, AND .002 GPS FP-6L / MIXED CEMENT AT 17.0 PPG WITH YIELD OF 0.99 CF/SX / DISPLACED WITH 1 BBL WATER AND 41 BBL 9.6# MUD FOR A													
	23:00	1	BALANCED PLUG													
23:00	1:00	2	TRIP OUT 9 STANDS DRILL PIPE / CIRCULATE BOTTOMS UP / TRIP OUT OF HOLE TO THE 2 7/8" TUBING													
1:00	2:00	1	SLIP & CUT 92' DRILLING LINE													
2:00	4:00	2	PJSM, RIG UP FRANKS TUBING TONGS AND LAY DOWN TUBING / RIG DOWN TUBING TONGS													
4:00	4:30	0.5	INSTALL WEAR BUSHING													
4:30	6:00	1.5	PICK UP BIT, MUD MOTOR, & MWD / SCRIBE & TEST MOTOR / TRIP IN HOLE TO SURFACE CASING SHOE													
NOTE: JERRY BARNES CALLED DAVE HACKFORD WITH UTAH DIVISION OF OIL GAS & MINING FOR APPROVAL AND NOTICE OF PLUG BACK AND KICK OFF ON 7/10/2014 AT 09:30.																
			PROGNOSIS	ACTUAL	TVD ACTUAL											
			WASATCH	5,329'	5,344'	5,209'										
			MASAVERDE	9,168'	9,153'	8,978'										
			CASTLEGATE	11,668'												
			BLACKHAWK	11,928'												
			SPRING CANYON	12,598'												
TOTAL HOURS:			24	TD	12,698'											
MUD REPORT																
MW		VIS	PV	YP	GELS		FLUID LOSS		SOLIDS	WATER	DAP	O/W	SAND			
INITIAL		10 MIN		API	HPHT	%	%	PPB	%	%						
9.4		32		2	3	2	4	10.2		4.0%	96%	6.1	0/96	TR		
CAKE		PH	PM	PF	MF	CL	HARDNESS	ECD	LCM	Daily Mud Cost		Cumulative				
1-32		9.0		0.01	.04	00	2,600	50		0.1%	\$802	\$100,742				
BIT REPORT																
BIT #	SIZE	MGF	TYPE	SERIAL NUMBER	JETS	DEPTH IN	DAY END/OUT	TOTAL FOOTAGE	TOTAL HOURS	WOB	RPM/MOTOR	ROP				
1	7 7/8"	SECURITY	MM65M	12424241	6-16	3,059'	7,407'	4,348'	66.0	15/18	60/68.7	65.9 FPH				
2	7 7/8"	SMITH	MDi616	JJ3382	6-16	7,407'	9,456'	2,049'	42.5	15/20	60/133	48.2 FPH				
3	7 7/8"	SECURITY	MM65D	12455019	6-17	7,373'	10,152'	2,779'	102.0	20/24	45/78	27.5 FPH				
4	7 7/8"	SECURITY	MM65D	12413378	6-16	10,152'						LEFT IN HOLE				
5	7 7/8"	SECURITY	MM65M	12367694	6-16											
BIT CONDITION		INNER ROWS	OUTER ROWS	DULL CHAR.		LOCATION	BEARINGS / SEALS		GAGE	OTHER	REASON PULLED					
PUMP REPORT																
PUMP #	MODEL	LINER SIZE	SPM	GPM	PRESSURE	ANNULAR VELOCITY		DC OD	DP OD	HOLE						
1	BOMCO	1600	5 1/2				DP	DC	6 1/2"	4 1/2"	7 7/8"					
2	BOMCO	1600	5 1/2													
		TOTAL	0	0												
BHA TOTAL LENGTH		BHA DESCRIPTION														
1023.35		BIT=1.00 / 7:8 6.4,.29 RPG, 1.5" MM=28.86 / NMPC=9.79 / HOS=1.71 / NMDC=29.32 / GAP SUB=4.29 / NMPC=9.95 / NMDC=30.87 / HWDP=907.56														
MUD MOTOR HOURS		HOURS ON JARS		BOP MAKE & TYPE					BOP TEST DATE & PRESSURE							
				11" SHAFFER LWS 5,000# DBL GATE & 11" SHAFFER 5,000# ANNULAR					15 Jun 14 5,000 PSI							
CASING RECORD			TOTAL DRILL GAS		TOUR CHECK			DEVIATION RECORD			KILL RATE @					
DEPTH			GAS		UNITS		DEPTH		INC		AZ		PUMP 1		PUMP 2	
SIZE			PROPOSED		ACTUAL		BGG		100		PICK UP					

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input checked="" type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/3/2014	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> DRILLING REPORT Report Date:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco notified UDOGM of decision to plug back well on 6/18/14 at 9:45AM Plug back took place 7/2/14. Plug #1 was set from 9308'-9078' with 68 sx of Class G cement. Plug #2 was set from 7697'-7324' with 128 sx of Class G cement. Cement was tagged for a PBTD of 7373'. Gasco kicked off and is drilling around old wellbore. See attached drilling reports for additional details.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> August 07, 2014		
<b>NAME (PLEASE PRINT)</b> Jessica Berg	<b>PHONE NUMBER</b> 303 996-1805	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/12/2014	

## DAILY DRILLING REPORT

## STRAP FISHING TOOLS

<b>TOTAL HOURS:</b>	24
---------------------	----

## BIT REPORT

BIT CONDITION
---------------

## PUMP REPORT

**BOTTOM HOLE ASSEMBLY**

2,500,000

CASING RECORD	
---------------	--

---

435-828-0601



## DAILY DRILLING REPORT

[illegible]

## DAILY DRILLING REPORT

## DAILY DRILLING REPORT

[illegible]



## DAILY DRILLING REPORT

## DAILY DRILLING REPORT

[illegible]

## DAILY DRILLING REPORT

[illegible]

Gasco Myton, Utah - Notification Form

CONFIDENTIAL

Operator GASCO PROD. Rig Name/# SST 54  
Submitted By SCOTT ALLRED Phone Number 435-828-0601  
Well Name/Number DESERT SPRINGS STATE 412-36-9-18  
Qtr/Qtr SW/NE Section 36 Township 9 S Range 18 E  
Lease Serial Number ~~ML 54171~~ ML 45171  
API Number 43047533240000

---

SPUD NOTICE – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time \_\_\_\_\_ AM ☐ PM ☐

---

CASING – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 7/27/2014 7:00 AM ☒ PM ☐

---

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks If you would like to witness, please call for a more exact time  
Thank You



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML45171
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		8. WELL NAME and NUMBER: Desert Springs State 412-36-9-18
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112	PHONE NUMBER: 303 996-1805 Ext	9. API NUMBER: 43047533240000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1462 FNL 1352 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH
		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>9/8/2014</b>	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input type="text" value="Temp Water Lines"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco intends to lay approximately 3,099' of 10" lay flat hose along the bar ditch of the road from the Desert Springs Evaporation Facility Pit #1 (South Pit) to the pad for the Desert Spring State 412-36-9-18, 422-36-9-18 and 424-36-9-18 (see attached map). All lay flat hose connections will be a twist and lock connection. Road crossings will have a 1 foot culvert put in place. Gasco intends to use produced water from the evap pond and treat it by running it through a 150 micron filter then injecting MC B-8614 Biocide in the line. It will be pumped into frac tanks on location. All pumps will have containment under them. Gasco also intends to use the line to pump flowback water to the evap facility. It is estimated the lines will be in use for approximately 30 days.

Gasco will monitor the lines for leaks at the startup and periodically throughout the operation

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Date:** September 02, 2014

**By:** 

**Please Review Attached Conditions of Approval**

NAME (PLEASE PRINT) Jessica Berg	PHONE NUMBER 303 996-1805	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 8/18/2014




**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**


**Sundry Conditions of Approval Well Number 43047533240000**

**The operation is approved as proposed. Approval from SITLA for the right-of way shall be obtained by Gasco Production Company.**



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 4/1/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION         </div> </div>	
OTHER: <span style="border: 1px solid black; padding: 2px;">Request for exception location</span>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Please see the attached exception location request with accompanying letters of agreement from all applicable parties within any portion of the 460-foot radius along the projected wellbore.		
<b>Accepted by the          Utah Division of          Oil, Gas and Mining          FOR RECORD ONLY          September 23, 2014</b>		
<b>NAME (PLEASE PRINT)</b> Jessica Berg	<b>PHONE NUMBER</b> 303 996-1805	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 3/29/2014	





March 26, 2014

Department of Natural Resources  
Utah Division of Oil Gas and Mining  
1594 West North Temple, Suite #1210  
Salt Lake City, Utah 84116

RE: Directional Drilling Exception Location Request  
Gasco Production Company  
**Desert Springs State 412-36-9-18**  
SHL: 1,462' FNL / 1,352' FEL (SWNE)  
BHL: 495' FNL / 660' FEL (NENE)  
Section 36 – Township 9 South, Range 18 East, SLBM  
Uintah County, Utah  
State Mineral Lease at SHL and BHL: ML-45171

To Whom It May Concern,

Pursuant to the filing of the filing of the Gasco Production Company ("Gasco") Utah Division of Oil Gas and Mining ("UDOGM") Application for Permit to Drill ("APD") for the Desert Springs State 412-36-9-18, Gasco hereby requests an exception to the UDOGM Rule R649-11 and R469-12 as amended under Docket No. 2012-011 and Cause 173-26 which states "... in the absence of a specific Board order otherwise addressing such directional drilling. The elimination of any offset limitations as between wells within each leasehold in the Subject Lands and the suspension of Utah Admin. Code Rules R649-10 and R649-12 (1) and (2), with the proviso that no well may be directionally drilled in any portion of a 460-foot radius along the projected wellbore intersects with a boundary of a lease without the approval of the Division or Board in accordance with Utah Admin. Code Rules R649-10 and R649-11 (1) and (2), is just and reasonable under the circumstances." Please find enclosed a copy of the Findings of Fact, Conclusions of Law and Order for Docket No. 2012-011 and Cause 173-26 for your reference.

Wapiti and Gasco Production Company control 100% of the leasehold in the spaced zones and formations; please find enclosed a copy of Wapiti Oil and Gas II, L.L.C and First Griffin Group L.L.C.'s consent to directionally drill the above referenced well. The State of Utah is the mineral interest owner on State Oil and Gas Lease ML-45171. In order to maximize recovery of the Wasatch formation and Mesaverde Group reservoir on the leasehold pursuant to the ten (10) acre density pattern set forth in the above mentioned Docket No. and Cause No., it is the belief that drilling at this surface location is necessary as an exception location to the amended Utah Admin. Code Rules R649-10 and R649-11 (1) and (2) to prudently and thoroughly develop the reservoir.

By locating the well at this surface location and directionally drilling, Gasco will be able to utilize existing roads, pipelines, and infrastructure in the area with minimal surface disturbance in accordance with the Gasco Environmental Impact Study cover this area, while producing the well in the most efficient manner for optimal resource recovery.

The producing interval of the above referenced well will only be located vertical from the permitted bottom hole location.

If you have any questions or concerns please feel free to contact me at (303) 996-1815.

Thank you again for your assistance, your prompt response is greatly appreciated.


Sincerely,

A handwritten signature in black ink, appearing to read 'Brandon Casey', with a stylized flourish extending from the bottom right.

Brandon Casey

Landman

cc: enclosures



February 10, 2014

Wapiti Oil & Gas II, L.L.C.  
800 Gessner, Suite #700  
Houston, TX 77024

RE: Directional Drilling Exception Location Consent Request  
Gasco Production Company  
**Desert Springs State 412-36-9-18**  
SHL: 1,462' FNL / 1,352' FEL (SWNE)  
BHL: 495' FNL / 660' FEL (NENE)  
Section 36 – Township 9 South, Range 18 East, SLBM  
Uintah County, Utah  
State Mineral Lease at SHL and BHL: ML-45171

To Whom It May Concern,

Pursuant to the filing of Gasco Production Company ("Gasco"), Utah Division of Oil Gas and Mining (UDOGM) Application for Permit to Drill ("APD") for the Desert Springs State 412-36-9-18, Gasco hereby requests an exception to UDOGM Rule R649-11 and R469-12 as amended under Docket No. 2012-011 and Cause 173-26 which states "... in the absence of a specific Board order otherwise addressing such directional drilling. The elimination of any offset limitations as between wells within each leasehold in the Subject Lands and the suspension of Utah Admin. Code Rules R649-10 and R649-12 (1) and (2), with the proviso that no well may be directionally drilled in any portion of a 460-foot radius along the projected wellbore intersects with a boundary of a lease without the approval of the Division or Board in accordance with Utah Admin. Code Rules R649-10 and R649-11 (1) and (2), is just and reasonable under the circumstances." Please find enclosed a copy of the Findings of Fact, Conclusions of Law and Order for Docket No. 2012-011 and Cause 173-26 for your reference.

The projected wellbore encroaches within a 460 foot radius of acreage within the above referenced oil and gas leases that are partially owned by you.

In order to maximize recovery of the Wasatch formation and Mesaverde Group reservoir on the leasehold pursuant to the ten (10) acre density pattern set forth in the above mentioned Docket No. and Cause No., it is the belief that drilling at this surface location is necessary as an exception location to the amended Utah Admin. Code Rules R649-10 and R649-11 (1) and (2) to prudently and thoroughly develop the reservoir. By locating the well at this surface location and directionally drilling, Gasco will be able to utilize existing roads, pipelines and infrastructure in the area with minimal surface disturbance in accordance with the Gasco Environmental Impact

Study covering this area, while producing the well in the most efficient manner for optimal resource recovery.


The producing interval of the above referenced well will only be located vertical from the permitted bottom hole location. Please find enclosed a copy of the survey plat showing both the surface hole location and bottom hole location for your reference.

If this meets with your approval, please so indicate by executing, dating, and returning one (1) original copy of this letter in the enclosed self-addressed stamped envelope.

If you have any questions or concerns please feel free to contact me at (303) 996-1815.

Thank you again for your assistance, your prompt response is greatly appreciated.

Sincerely,



Brandon Casey  
Landman

cc: enclosures

Agreed and accepted this 12<sup>th</sup> day of February, 2014.

WAPITI OIL AND GAS II, L.L.C.

By: W. Allen Ricks

Title: V.P. Rockers





February 10, 2014

First Griffin Group, LLC  
200 West Adams St., Suite 1015  
Chicago, IL 60606

RE: Directional Drilling Exception Location Consent Request  
Gasco Production Company  
**Desert Springs State 412-36-9-18**  
SHL: 1,462' FNL / 1,352' FEL (SWNE)  
BHL: 495' FNL / 660' FEL (NENE)  
Section 36 – Township 9 South, Range 18 East, SLBM  
Uintah County, Utah  
State Mineral Lease at SHL and BHL: ML-45171

To Whom It May Concern,

Pursuant to the filing of Gasco Production Company ("Gasco"), Utah Division of Oil Gas and Mining (UDOGM") Application for Permit to Drill ("APD") for the Desert Springs State 412-36-9-18, Gasco hereby requests an exception to UDOGM Rule R649-11 and R469-12 as amended under Docket No. 2012-011 and Cause 173-26 which states "... in the absence of a specific Board order otherwise addressing such directional drilling. The elimination of any offset limitations as between wells within each leasehold in the Subject Lands and the suspension of Utah Admin. Code Rules R649-10 and R649-12 (1) and (2), with the proviso that no well may be directionally drilled in any portion of a 460-foot radius along the projected wellbore intersects with a boundary of a lease without the approval of the Division or Board in accordance with Utah Admin. Code Rules R649-10 and R649-11 (1) and (2), is just and reasonable under the circumstances." Please find enclosed a copy of the Findings of Fact, Conclusions of Law and Order for Docket No. 2012-011 and Cause 173-26 for your reference.

The projected wellbore encroaches within a 460 foot radius of acreage within the above referenced oil and gas leases that are partially owned by you.

In order to maximize recovery of the Wasatch formation and Mesaverde Group reservoir on the leasehold pursuant to the ten (10) acre density pattern set forth in the above mentioned Docket No. and Cause No., it is the belief that drilling at this surface location is necessary as an exception location to the amended Utah Admin. Code Rules R649-10 and R649-11 (1) and (2) to prudently and thoroughly develop the reservoir. By locating the well at this surface location and directionally drilling, Gasco will be able to utilize existing roads, pipelines and infrastructure in the area with minimal surface disturbance in accordance with the Gasco Environmental Impact

Study covering this area, while producing the well in the most efficient manner for optimal resource recovery.


The producing interval of the above referenced well will only be located vertical from the permitted bottom hole location. Please find enclosed a copy of the survey plat showing both the surface hole location and bottom hole location for your reference.

If this meets with your approval, please so indicate by executing, dating, and returning one (1) original copy of this letter in the enclosed self-addressed stamped envelope.

If you have any questions or concerns please feel free to contact me at (303) 996-1815.

Thank you again for your assistance, your prompt response is greatly appreciated.

Sincerely,




Brandon Casey  
Landman

cc: enclosures

Agreed and accepted this 24<sup>th</sup> day of MARCH, 2014.

FIRST GRIFFIN GROUP, LLC

By:   
Title: MANAGER

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 10/27/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE   <input type="checkbox"/> CHANGE TO PREVIOUS PLANS   <input type="checkbox"/> CHANGE WELL STATUS   <input type="checkbox"/> DEEPEN   <input type="checkbox"/> OPERATOR CHANGE   <input type="checkbox"/> PRODUCTION START OR RESUME   <input type="checkbox"/> REPERFORATE CURRENT FORMATION   <input type="checkbox"/> TUBING REPAIR   <input type="checkbox"/> WATER SHUTOFF   <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING   <input type="checkbox"/> CHANGE TUBING   <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS   <input type="checkbox"/> FRACTURE TREAT   <input type="checkbox"/> PLUG AND ABANDON   <input type="checkbox"/> RECLAMATION OF WELL SITE   <input type="checkbox"/> SIDETRACK TO REPAIR WELL   <input type="checkbox"/> VENT OR FLARE   <input type="checkbox"/> SI TA STATUS EXTENSION   <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR   <input type="checkbox"/> CHANGE WELL NAME   <input type="checkbox"/> CONVERT WELL TYPE   <input type="checkbox"/> NEW CONSTRUCTION   <input type="checkbox"/> PLUG BACK   <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION   <input type="checkbox"/> TEMPORARY ABANDON   <input checked="" type="checkbox"/> WATER DISPOSAL   <input type="checkbox"/> APD EXTENSION           OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Gasco intends to primarily dispose of produced water at the Desert Spring State Evaporation Facility and the Eight Mile Flat Evaporation Facility owned by Monarch Natural Gas, LLC. Gasco may also utilize the following State approved disposal facilities: Brennan Bottom Disposal, Environmental Energy Innovations, Integrated Water Management, LLC, Iowa Tanklines, Inc., R N Industries, Inc., and Western Water Solutions.		
<b>NAME (PLEASE PRINT)</b> Lindsey J. Cooke		<b>PHONE NUMBER</b> 303 996-1834
<b>SIGNATURE</b> N/A		<b>TITLE</b> Production Tech
<b>DATE</b> 10/30/2014		<div style="text-align: right;"> <b>Accepted by the Utah Division of Oil, Gas and Mining</b>  <b>FOR RECORD ONLY</b>          October 31, 2014       </div>

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. API NUMBER:</b> 43047533240000
<b>PHONE NUMBER:</b> 303 996-1805 Ext		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/27/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This well was put on production and had first sales at 4:00 PM on 10/27/2014.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> October 31, 2014		
<b>NAME (PLEASE PRINT)</b> Lindsey J. Cooke	<b>PHONE NUMBER</b> 303 996-1834	<b>TITLE</b> Production Tech
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/30/2014	



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

RECEIVED  
FORM 6  
OCT 22 2014

Div. of Oil, Gas & Mining

**ENTITY ACTION FORM**

Operator: Gasco Production Company Operator Account Number: N 2575  
Address: 7979 E. Tufts Ave., Suite 1150  
city Denver  
state CO zip 80237 Phone Number: (303) 996-1834

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304753324	Desert Spring State 412-36-9-18		SWNE	36	9S	18E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
E	19454	19783	4/14/2014			10/31/14	
Comments: Please assign all 3 wells to the same entity.							

**CONFIDENTIAL**

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304753328	Desert Spring State 422-36-9-18		SWNE	36	9S	18E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
E	19458	19783	4/14/2014			10/31/14	
Comments: Please assign all 3 wells to the same entity.							

**CONFIDENTIAL**

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304753325	Desert Spring State 424-36-9-18		SWNE	36	9S	18E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
E	19455	19783	4/14/2014			10/31/14	
Comments: Please assign all 3 wells to the same entity.							

**CONFIDENTIAL**

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Lindsey Cooke

Name (Please Print)

Signature

Production Tech

Title

10/22/2014

Date

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML45171			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  <b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>2. NAME OF OPERATOR:</b> GASCO PRODUCTION COMPANY		<b>8. WELL NAME and NUMBER:</b> Desert Springs State 412-36-9-18			
<b>3. ADDRESS OF OPERATOR:</b> 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		<b>9. API NUMBER:</b> 43047533240000			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1462 FNL 1352 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 18.0E Meridian: S		<b>9. FIELD and POOL or WILDCAT:</b> 8 MILE FLAT NORTH  <b>COUNTY:</b> UINTAH  <b>STATE:</b> UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
<b>TYPE OF SUBMISSION</b>  <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 10/27/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<b>TYPE OF ACTION</b>  <table style="width: 100%; border: none;"> <tr> <td style="vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </td> <td style="vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <span style="border: 1px solid black; padding: 2px;">Production Facilities &amp; Meas</span> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; padding: 2px;">Production Facilities &amp; Meas</span>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; padding: 2px;">Production Facilities &amp; Meas</span>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Gasco intends to use the following production facilities and measurement methods on the Desert Spring States 412-36-9-8, Desert Spring State 422-36-9-18 and the Desert Spring State 424-36-9-18 which share a common pad: Each well will be produced through its own three-phase separator. Gas will be metered through an electronic flow meter, a Total Flow XFCG4, then to a common sales meter. Liquids from each well will flow to individual 400 bbl tanks where water and condensate will be gauged regularly. Condensate will be manually skimmed into a common 400 bbl sales tank. Only one tank will be skimmed at a time in order to allow for gauging and tracking of the condensate from each well. These wells share the same lease with common ownership, and are being produce from the same formations. It has also been requested that all three wells share a common entity number for reporting purposes.					
<b>NAME (PLEASE PRINT)</b> Lindsey J. Cooke		<b>PHONE NUMBER</b> 303 996-1834			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Production Tech  <b>DATE</b> 10/30/2014			

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8  
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☐ OTHER \_\_\_\_\_b. TYPE OF WORK:  
NEW WELL ☐ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

3. ADDRESS OF OPERATOR:

CITY

STATE

ZIP

PHONE NUMBER:

4. LOCATION OF WELL (FOOTAGES)

AT SURFACE:

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:

9. API NUMBER:

10 FIELD AND POOL, OR WILDCAT

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,  
MERIDIAN:

12. COUNTY

13. STATE

UTAH

14. DATE SPUDDED:

15. DATE T.D. REACHED:

16. DATE COMPLETED:

ABANDONED ☐READY TO PRODUCE ☐

17. ELEVATIONS (DF, RKB, RT, GL):

18. TOTAL DEPTH: MD

TVD

19. PLUG BACK T.D.: MD

TVD

20. IF MULTIPLE COMPLETIONS, HOW MANY? \*

21. DEPTH BRIDGE MD

PLUG SET:

TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

23.

WAS WELL CORED?

NO ☐YES ☐

(Submit analysis)

WAS DST RUN?

NO ☐YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☐YES ☐

(Submit copy)

## 24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED

## 25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

## 26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A)				
(B)				
(C)				
(D)				

## 27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

## 28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

WAS WELL HYDRAULICALLY FRACTURED?

YES ☐NO ☐

IF YES -- DATE FRACTURED:

DEPTH INTERVAL

AMOUNT AND TYPE OF MATERIAL

## 29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION  
☐ GEOLOGIC REPORT  
☐ CORE ANALYSIS  
☐ DST REPORT  
☐ OTHER: \_\_\_\_\_  
☐ DIRECTIONAL SURVEY

## 30. WELL STATUS:

**31. INITIAL PRODUCTION****INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL B (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL C (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL D (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)****33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**34. FORMATION (Log) MARKERS:**

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

**35. ADDITIONAL REMARKS (Include plugging procedure)**

**36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.**

NAME (PLEASE PRINT) \_\_\_\_\_ TITLE \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



**Gasco Production Company**

Desert Spring State 412-36-9-18

NE SW of Section 36-T9S-R18E

Uintah County Utah,

**43-047-53324**

**Completion**

- 9/14/14 MIRU Baker logging. RIH w/RPM log to TD and log well. SDFD.
- 10/6/14 MIRU RBS psi tester and test casing to 9,800 psi and monitor for 10 min, test good. Bleed off psi and RDMO RBS. SDFD.
- 10/13/14 Have safety meeting, (perf guns). MIRU The Perforators. MU and RIH w/2 ¾" perf guns. **Perf stage-1 Spring Canyon f/12,584-88', 12,598-602', 12,608-12', POOH 74' w/2 ¾" guns 15 gram charge, .38 EH 36" pen 120 degree phase 3 spf. Secure well for night and SDFD.**
- 10/14/14 MIRU Halliburton frac crew. Have safety meeting, (pumping psi, communication). Prime and test pump and lines to 9,800 psi, test good. FD 0 sicp. Break dn perfs w/3,050 psi @ 5 bpm. Get rate up to 28 bpm w/3,850 psi, SD. ISIP 3,203. Produced water FR slick water frac well w/96,100# 20/40 Premium white sand, 3,933 bbls Produced FR slick water, and flushed w/187 bbls Produced FR slick water. SD, ISIP 4,814 MR 53.4 bpm, AR 53.4 bpm, MP 8,912, AP 7,772. Open well up to FB @ 5:00 p.m. and 0 psi on the well. Leave well open to FB for night to monitor psi. SDFD.
- 10/15/14 Fd well dead. RU and pump 30 bbls @ 10 bpm and and caught psi. psi went up to 8,000. SD and well slowly bled off to 0. Try to flush again and psi came up to 8,500 psi, SD. Well bled off to 0. MU and RIH w/3.65 gauge ring to 12,525', POOH. When running gauge ring fd fluid level @ 110' from surface. MU and RIH w/plug. **Set HES 10k Obsidian FTFP w/soluplug @ 12,520'.** POOH. MU plug and guns and RIH. Pressure well up to 4,000 psi and **set second HES 10k Obsidian FTFP w/soluplug @ 12,500'.** **Perf stage-2 Kenilworth/Aberdeen f/12,364-65', 12,372-74', 12,422-23', 12,449-50', 12,476-77', 12,486-88' w/2 ¾" gun, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/7,431 @ 4 bpm. Get rate up to 24 w/8,076 psi and SD, ISIP 4,930 FG .85 calculated holes open 6.8, (28.1%). Produced FR slick water frac well w/76,060# 20/40 Premium white sand, 3,183 bbls Produced FR slick water, and flushed w/193 bbls Produced FR slick water, spot 250 gal 15% HCL during flush for next set of perfs. SD, ISIP 4,747 FG .84 MR 50 bpm, AR 46.6 bpm, MP 8,810 AP 8,375. Leave well shut in to monitor psi. SDFD.**

- 10/16/14 Have safety meeting, (multiple operations). FD 4,600 sicmp. MU and RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 12,130'.** **Perf stage-3 Desert/Grassy** f/11,940-41', 11,960-61', 11,988-89', 12,002-03', 12,011-12', 12,032-33', 12,048-49', 12,066-67', 12,092-93', 12,104-05' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH Ru to frac. Break dn perfs w/8,577 @ 5 bpm. Get rate up to 40 bpm w/8,130 psi and SD, ISIP 4,240 FG .81, calculated holes open 12.3 (41%). Produced FR slick water frac well w/110,200# 20/40 Premium white sand, 5,359 bbls Produced FR slick water, and flushed w/188 bbls Produced FR slick water. Pumped 500 gal 15% HCL during flush for next set of perfs. SD, ISIP 4,314 FG .81. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 11,646'.** **Perf stage-4 Lower Mesaverde** f/11,329-30', 11,356-57', 11,388-89', 11,472-73', 11,482-83', 11,510-11', 11,536-37', 11,564-66', 11,590-91', 11,603-04', 11,620-21' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/6,749 @ 4.9 bpm. Get rate up to 38.6 bpm and SD. ISIP, 4,369 FG .84 calculated holes open 18, (50%). Produced water FR slick water frac well w/144,200# 20/40 Premium white sand, 5,456 bbls Produced FR slick water, and flushed w/168 bbls Produced FR slick water. SD, ISIP 4,381 FG .84 MR 60.3 bpm, AR 59.4 bpm, MP 8,092 psi, AP 8,250 psi. Open well up to flow back @ 5:30 p.m. w/4,300 on a 14/64 ck. SDFD.
- 10/17/14 Have safety meeting, (pumping psi). Fd well flowing w/4,000 on a 14/64 ck. Made 1,056 bbls in 11 hrs 30 min. TR 1,056 bbls, BLWTR 17,612 bbls. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 11,294'.** **Perf stage-5 Lower Mesaverde** f/10,969-70', 10,992-93', 11,013-14', 11,039-40', 11,062-63', 11,121-22', 11,150-51', 11,157-58', 11,212-13', 11,242-43', 11,264-65' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. Ru to frac. Break dn perfs w/5,381 @ 5 bpm. Get rate up to 42 bpm and SD. ISIP 4,139 FG .83 calculated holes open 12.4, (37.6%). Produced water FR slick water frac well w/128,900# 20/40 Premium white sand, 5,550 bbls Produced FR slick water, and flushed w/17 bbls Produced FR slick water. SD, MR 60.3 bpm, AR 55.3 bpm, MP 9,598 AP 8,169 psi. Screened out, cut job 3,100# short. Open well up to FB @ 3:50 p.m. w/3,500 on a 14/64 ck. SDFD. Total fluid pumped 24,235 bbls.
- 10/18/14 Have safety meeting, (wireline). Fd well flowing @ 3,700 on a 14/64 ck. Made 1,247 bbls in 13 hrs 13 min, TR 2,303 bbls, BLWTR 21,932 bbls. RU and pump flush on well w/acid for next set of perfs. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 10,945'.** **Perf stage-6 Lower Mesaverde** f/10,740-41', 10,764-65', 10,784-86', 10,812-13', 10,854-56', 10,871-72', 10,918-20' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/5,283 @ 5 bpm. Get rate up to 40.4 bpm and SD. ISIP, 4,054 FG

.83 calculated holes open 20.5, (68.4%). Produced FR slick water frac well w/120,700# 20/40 Premium white sand, 4,808 bbls Produced FR slick water, and flushed w/166 bbls Produced FR slick water. SD, ISIP 4,134 FG .84 MR 58.7 bpm, AR 56.3 bpm, MP 8,700 psi, AP 8,095 psi. Open well up to FB @ 6:17 w/3,700 on a 14/64 ck. Total volume pumped 29,372 SDFD.

10/19/14 Have safety meeting, (pumping psi). Fd well flowing @ 3,500 on a 14/64 ck. Made 915 bbls in 11 hrs 17 min. TR 3,218 bbls, BLWTR 26,154 bbls. Pumped flush on well bore w/HCL for next set of perfs. RIH w/ plug and guns. **Set HES 10k obsidian FTFP w/soluplug @ 10,468' perf. Stage-7 Upper Mesaverde** f/ 10,130-31', 10,141'-42', 10,173-74', 10,216-17', 10,328-29', 10,343-44', 10,378-79', 10,392-93', 10,442-43'. w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. R/U to frac. Break dn perfs w/5,554 @ 5 bpm. Get rate up to 44 bpm and SD. ISIP 3,833 FG .81 calculated holes open 23, (85%). Produced FR slick water frac well w/144,100# 20/40 Premium white sand, 6,074 bbls Produced FR slick water, and flushed w/151 bbls Produced FR slick water. SD, ISIP 3,833, FG .86 MR 60.2 bpm, AR 59.4 bpm, MP 8,428, AP 7,797 psi. Open well to flow back @ 7:00 p.m. w/3,600 on a 14/64 ck. SDFD. Total fluid pumped 35,597 bbls.

10/20/14 Have safety meeting, (pumping acid). Fd well flowing @ 3,600 on a 16/64 Made 1,129 bbls in 10 hrs, TR 4,347 bbls, BLWTR 31,250 bbls. Pump 135 bbls flush on well w/250 gal 15% HCL acid for next set of perfs. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 10,030'. Perf stage-8 Upper Mesaverde** f/9,586-87', 9,608-09', 9,632-33', 9,760-61', 9,772-73', 9,804-05', 9,838-39', 9,854-55', 9,895-96', 9,968-69', 9,985-86', 10,000-01' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/4,508 @ 5.1 bpm. SD, ISIP 3,174 FG .79 calculated holes open 14.5, (40.3%). Produced FR slick water frac well w/144,300# 20/40 Premium white sand, 5,374 bbls Produced FR slick water, and flushed w/152 bbls Produced FR slick water. SD, ISIP 3,413 FG .81 MR 64 bpm, AR 57.9 bpm, MP 8,568 psi, AP 7,345 psi. Open well up to FB @ 3:00 a.m. w/3,000 on a 16/64 ck. SDFD. Total fluid pumped, 41,124 bbls.

10/21/14 Have safety meeting, (slips, trips, falls). Fd well flowing @ 3,000 on a 16/64 ck. Made 1,446 bbls in 13 hrs. TR 5,793 bbls, BLWTR 35,331 bbls. RU and pump 142 bbl flush on well w/250 gal 15% HCL acid for next set of perfs. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 9,546'. Perf stage-9 Upper Mesaverde/Dark Canyon** f/9,186-87', 9,199-9,200', 9,209-10', 9,246-47', 9,348-49', 9,360-61', 9,380-81', 9,412-13', 9,426-27', 9,526-27', 9,456-57', 9,522-24' w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/4,260 @ 5 bpm. Get rate up to 43 bpm and SD.

ISIP, 3,165 FG .79 calculated holes open 13.6, (37.9%). Produced FR slick water frac well w/156,100# 20/40 Premium white sand, 6,394 bbls Produced FR slick water, and flushed w/146 bbls Produced FR slick water. Pumped 500 gals 15% HCL acid during flush for next set of perfs. SD, ISIP 3446 FG .82 MR 61 bpm, AR 60 bpm, MP 8,612, AP 7,148 psi. RIH w/plug and guns. **Set HES 10k Obsidian FTFP w/soluplug @ 8,910'. Perf stage-10 Wasatch f/8,578-79', 8,589-90', 8,674-75', 8,802-03', 8,839-40', 8,864-66', 8,886-87'** w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. RU to frac. Break dn perfs w/4,514 @ 5 bpm. Get rate up to 44 bpm and SD. ISIP 3,311 FG .81, calculated holes open 18.6 FG .81 Produced FR slick water frac well w/84,100# 20/40 Premium white sand, 3,728 bbls Produced FR slick water, and flushed w/128 bbls Produced FR slick water. SD, ISIP 3,408 FG .81 MR 60.5 bpm, AR 59.4 bpm, MP 8,006 psi, AP 7,516 psi. Open well up to FB @ 5:00 p.m. w/3,000 on a 16/64 ck. SDFD.

10/22/14 Have safety meeting, (wireline). Fd well flowing @ 2,100 on a 16/64 ck. made 981 bbls in 10 hrs 45 min. TR 6,774 bbls, BLWTR 44,748 bbls. Pump 118 bbls flush on well w/250 gal 15% HCL for next set of perfs. RIH w/plug and guns. **Set HES 10k Obsidian FTFP @ 8,322'**, when tried to set plug the plug did not set all the way. Pressure up on well to 4,500 psi and plug set. Collar locator failed. POOH. Rehead and RIH w/guns. **Perf stage-11 Wasatch f/7,964-65', 8,043-44', 8,160-61', 8,174-75', 8,212-13', 8,278-79', 8,300-02'** w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/5,578 @ 4.6 bpm. Get rate up to 38.8 bpm and SD. ISIP 2,296 FG .70 calculated holes open 11.2 (46.8%). Produced FR slick water frac well w/120,000# 20/40 Premium white sand, 4,705 bbls Produced FR slick water, and flushed w/128 bbls Produced FR slick water. SD, ISIP 2,407 FG .71 MR 64.2 bpm, AR 60 bpm, MP 8,722 psi, AP 7,108 psi. RIH w/plug and guns. **Set 10k Obsidian FTFP @ 7,360'. Perf stage-12 Wasatch f/6,944-45', 6,978-79', 6,988-89', 7,142-43', 7,222-24', 7,322-23', 7,336-38'** w/2 ¾" guns, Titan 15 gram charges, .38 EH, 36" Pen, 120 degree phase, 3 spf. POOH. RU to frac. Break dn perfs w/1,665 @ 5 bpm. Get rate up to 39 bpm and SD. ISIP, 1,168 FG .58 calculated holes open 13.3, (49.2%). Produced FR slick water frac well w/100,000# 20/40 Premium white sand, 3,919 bbls Produced FR slick water, and flushed w/103 bbls Produced FR slick water. SD, ISIP 1,509 FG .61 MR 60.6 bpm, AR 60.1 bpm, MP 6,821 psi, AP 5,322 psi. Open well up to FB @ 7:00 p.m. w/1,000 on a 16/64 ck. SDFD.

10/23/14 7:00 a.m. fd well flowing @ 1,000 psi on a 16/64 ck. Made 653 bbls in 12 hrs, TR 7,427 bbls, BLWTR 52,950 bbls.



10/24/14 7:00 a.m. fd well flowing @ 1,100 psi on a 16/64 ck. Made 1380 bbls in 24 hrs, TR 8,807 bbls, BLWTR 52,950 bbls.



10/25/14 7:00 a.m. fd well flowing @ 900 psi on a 16/64 ck. Made 2,113 bbls in 24 hrs, TR 10,920 bbls, BLWTR 52,950 bbls. 10/25/14 Held safety meeting: (PSI). R/U Coil tubing Schlumberger test flowback lines and bope to 7k (held), RIH w/ Weatherford, s new 33/4'' 4- bladed mill, used mudmotor. FCP @ 850. Tag 1<sup>st</sup> plug @ 7,375' c/o plug in 14 mins FCP @ 850. Tag 2<sup>nd</sup> plug @ 8,355' c/o plug in 29 mins FCP @ 700. Tag 3<sup>rd</sup> plug @ 8,935' c/o plug in 23 mins FCP @ 750. Tag 4<sup>th</sup> plug @ 9,569' c/o plug in 35 mins FCP @ 1,850. Tag 5<sup>th</sup> plug @ 10,058' c/o plug in 26 mins FCP @ 1,900. Tag 6<sup>th</sup> plug @ 10,496' c/o plug in 22 mins FCP @ 1,850. Tag 7<sup>th</sup> plug @ 10,971' c/o plug in 26 mins FCP @ 1,700. Tag 8<sup>th</sup> plug @ 11,325' c/o plug in 9 mins FCP @ 2,300. Tag 9<sup>th</sup> plug @ 11,676' c/o plug in 30 mins FCP @ 2,400. Tag 10<sup>th</sup> plug @ 12,161' c/o plug in 20 mins FCP @ 2,600. Tag 11<sup>th</sup> plug @ 12,542' c/o plug in 7 mins FCP @ 2,800. RIH, Tag remaining part of plug @ 12,630', mill kept stalling out pulling over. Coil depth @ 12,593'- Correction @ 12,630' (18' of rat hole). Pumped 20 bbl sweep. POOH. FCP @ 2,700. SWI. Bled off, removed mill and mudmotor, restabbed on well, blew coil dry w/80,000 CF of Nitrogen. RDMO Schlumberger. Flow well on 16/64 Choke @ 2,700 PSI. Turn well over to flowback crew.

10/26/14 Drilled out Plugs turn back to flow back @ 12:10 a.m. 7:00 a.m. fd well flowing @ 2,300 psi on a 16/64 ck. Made 498 bbls in 7 hrs, TR 11,418 bbls, BLWTR 54,494 bbls.

10/27/14 7:00 a.m. well flowing @ 2,100 psi on a 16/64 ck. Made 1,013 bbls in 24 hrs, TR 12,431 bbls, BLWTR 53,481 bbls. Shut well in to rig up for sales @ 11:00 a.m. w/2,100 on a 16/64 ck. Made 194 bbls in 4 hrs. TR 12,625 bbls, BLWTR 53,287 bbls. Open well up to first sales @ 4:00 p.m.



Company: Gasco Energy  
Project: Uintah County, UT NAD27  
Site: Desert Springs  
Well: Desert Springs State #412-36-9-18  
Wellbore: ST-1  
Design: ST-1



#### Well Details: Desert Springs State #412-36-9-18

+N/-S	+E/-W	North	East	Latitude	Longitude	Slot
0.00	0.00	607976.68	2466005.56	39° 59' 26.379 N	109° 50' 12.030 W	

#### REFERENCE INFORMATION

Co-ordinate (N/E) Reference: Well Desert Springs State #412-36-9-18, True North  
Vertical (TVD) Reference: GL 4912' & RKB 25' @ 4937.00ft (SST 54)  
Section (VS) Reference: Slot - (0.00N, 0.00E)  
Measured Depth Reference: GL 4912' & RKB 25' @ 4937.00ft (SST 54)  
Calculation Method: Minimum Curvature

#### PROJECT DETAILS: Uintah County, UT NAD27

Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: Utah Central 4302

System Datum: Mean Sea Level

Plan: ST-1

13:24, September 22 2014  
Created By: Mel Mireles

RECEIVED: DEC 11, 2014

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	SDI OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Grand Junction District

<b>Project</b>	Uintah County, UT NAD27		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

Site	Desert Springs				
Site Position:		Northing:	607,976.71 usft	Latitude:	39° 59' 26.380 N
From:	Lat/Long	Easting:	2,466,005.55 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	1.07 °

Well	Desert Springs State #412-36-9-18					
Well Position	+N/-S	0.00 ft	Northing:	607,976.68 usft	Latitude:	39° 59' 26.379 N
	+E/-W	0.00 ft	Easting:	2,466,005.56 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	0.00 ft	Ground Level:	4,912.00 ft

<b>Wellbore</b>	SDI OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	BGGM2014	7/2/2014	10.94	65.71	51,868

<b>Design</b>	OH				
<b>Audit Notes:</b>					
<b>Version:</b>	1.0	<b>Phase:</b>	ACTUAL	<b>Tie On Depth:</b>	2,990.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>	
	0.00	0.00	0.00	36.69	

<b>Survey Program</b>	<b>Date</b>	8/20/2014			
<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>	
145.00	2,990.00	Survey #1 (GyroData OH)	MWD	MWD - Standard	
2,990.00	7,327.00	Survey #1 - MWD Survey (SDI OH)	MWD	MWD - Standard	
7,398.00	10,093.00	Survey #2 - SDI MWD Survey (SDI OH)	MWD	MWD - Standard	

<b>Survey</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Vertical Section (ft)</b>	<b>Dogleg Rate (°/100ft)</b>	<b>Build Rate (°/100ft)</b>	<b>Turn Rate (°/100ft)</b>	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
145.00	0.92	328.48	144.99	0.99	-0.61	0.43	0.63	0.63	0.00	
237.00	0.92	334.19	236.98	2.29	-1.32	1.05	0.10	0.00	6.21	
329.00	2.95	28.33	328.93	5.04	-0.51	3.73	2.74	2.21	58.85	
425.00	6.33	38.61	424.60	11.35	3.96	11.47	3.61	3.52	10.71	
519.00	6.99	40.81	517.97	19.73	10.93	22.35	0.75	0.70	2.34	
612.00	6.24	38.70	610.35	27.95	17.79	33.05	0.85	-0.81	-2.27	
706.00	5.19	41.34	703.88	35.13	23.79	42.39	1.15	-1.12	2.81	
800.00	5.05	42.92	797.51	41.36	29.42	50.74	0.21	-0.15	1.68	

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	SDI OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
895.00	5.19	43.80	892.13	47.52	35.24	59.16	0.17	0.15	0.93
989.00	4.84	32.55	985.77	53.93	40.32	67.33	1.11	-0.37	-11.97
1,083.00	4.57	33.69	1,079.45	60.39	44.53	75.03	0.30	-0.29	1.21
1,182.00	4.18	34.66	1,178.16	66.64	48.77	82.57	0.40	-0.39	0.98
1,274.00	5.01	35.63	1,269.87	72.66	53.02	89.94	0.91	0.90	1.05
1,369.00	5.67	36.42	1,364.45	79.81	58.22	98.78	0.70	0.69	0.83
1,461.00	5.71	36.50	1,456.00	87.14	63.64	107.90	0.04	0.04	0.09
1,556.00	5.89	37.12	1,550.51	94.83	69.39	117.50	0.20	0.19	0.65
1,650.00	6.29	36.24	1,643.98	102.83	75.35	127.48	0.44	0.43	-0.94
1,744.00	6.29	32.90	1,737.42	111.31	81.19	137.76	0.39	0.00	-3.55
1,839.00	6.20	30.53	1,831.85	120.09	86.62	148.06	0.29	-0.09	-2.49
1,934.00	6.24	31.49	1,926.29	128.92	91.92	158.30	0.12	0.04	1.01
2,030.00	5.63	29.38	2,021.78	137.47	96.96	168.16	0.67	-0.64	-2.20
2,126.00	5.14	31.23	2,117.36	145.25	101.50	177.12	0.54	-0.51	1.93
2,220.00	4.88	33.78	2,211.00	152.17	105.90	185.30	0.36	-0.28	2.71
2,316.00	5.71	31.49	2,306.59	159.64	110.67	194.14	0.89	0.86	-2.39
2,408.00	5.63	34.22	2,398.14	167.27	115.60	203.20	0.31	-0.09	2.97
2,503.00	5.67	36.33	2,492.68	174.91	121.00	212.55	0.22	0.04	2.22
2,599.00	5.63	35.10	2,588.21	182.58	126.52	222.00	0.13	-0.04	-1.28
2,692.00	5.67	32.99	2,680.76	190.17	131.64	231.14	0.23	0.04	-2.27
2,788.00	5.85	39.58	2,776.27	197.91	137.34	240.76	0.71	0.19	6.86
2,879.00	5.67	40.46	2,866.81	204.91	143.21	249.88	0.22	-0.20	0.97
2,971.00	5.41	38.35	2,958.38	211.77	148.85	258.75	0.36	-0.28	-2.29
2,990.00	5.36	38.09	2,977.30	213.17	149.96	260.53	0.29	-0.26	-1.37
3,052.00	5.30	38.70	3,039.03	217.68	153.53	266.29	0.13	-0.10	0.98
3,147.00	4.70	37.60	3,133.67	224.19	158.65	274.57	0.64	-0.63	-1.16
3,242.00	5.70	30.00	3,228.28	231.36	163.38	283.14	1.28	1.05	-8.00
3,337.00	5.40	27.00	3,322.83	239.43	167.77	292.24	0.44	-0.32	-3.16
3,432.00	5.40	31.30	3,417.41	247.23	172.12	301.09	0.43	0.00	4.53
3,527.00	6.30	38.40	3,511.92	255.14	177.68	310.75	1.21	0.95	7.47
3,622.00	7.60	45.10	3,606.22	263.66	185.37	322.18	1.61	1.37	7.05
3,717.00	9.60	45.00	3,700.15	273.69	195.42	336.23	2.11	2.11	-0.11
3,811.00	11.20	43.50	3,792.60	285.86	207.25	353.05	1.73	1.70	-1.60
3,907.00	11.70	41.50	3,886.69	299.91	220.12	372.01	0.66	0.52	-2.08
4,002.00	14.00	38.60	3,979.31	316.11	233.67	393.10	2.51	2.42	-3.05
4,094.00	16.60	38.80	4,068.04	335.05	248.85	417.36	2.83	2.83	0.22
4,188.00	19.20	36.60	4,157.48	357.93	266.49	446.24	2.86	2.77	-2.34
4,283.00	21.40	31.90	4,246.58	385.19	284.96	479.14	2.88	2.32	-4.95
4,379.00	23.80	31.50	4,335.20	416.58	304.34	515.88	2.51	2.50	-0.42
4,474.00	25.00	32.70	4,421.72	449.82	325.20	555.00	1.37	1.26	1.26
4,569.00	23.70	32.10	4,508.26	482.88	346.19	594.06	1.39	-1.37	-0.63
4,665.00	22.50	33.20	4,596.56	514.60	366.51	631.63	1.33	-1.25	1.15
4,760.00	24.00	33.70	4,683.85	545.89	387.18	669.07	1.59	1.58	0.53



## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	SDI OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,856.00	25.60	36.80	4,771.00	578.74	410.44	709.31	2.15	1.67	3.23
4,951.00	26.20	35.60	4,856.45	612.23	434.94	750.80	0.84	0.63	-1.26
5,045.00	25.40	35.20	4,941.08	645.57	458.64	791.70	0.87	-0.85	-0.43
5,141.00	23.60	33.50	5,028.44	678.42	481.12	831.48	2.01	-1.88	-1.77
5,236.00	24.20	33.80	5,115.29	710.46	502.45	869.91	0.64	0.63	0.32
5,331.00	24.50	34.30	5,201.84	742.91	524.38	909.04	0.38	0.32	0.53
5,426.00	24.00	33.20	5,288.46	775.35	546.06	948.00	0.71	-0.53	-1.16
5,521.00	24.00	33.10	5,375.24	807.71	567.19	986.57	0.04	0.00	-0.11
5,616.00	22.00	31.70	5,462.69	839.03	587.09	1,023.58	2.18	-2.11	-1.47
5,711.00	17.40	36.30	5,552.11	865.64	604.86	1,055.53	5.11	-4.84	4.84
5,807.00	15.60	37.60	5,644.15	887.43	621.24	1,082.79	1.91	-1.88	1.35
5,902.00	15.60	37.50	5,735.65	907.69	636.81	1,108.34	0.03	0.00	-0.11
5,997.00	13.20	38.10	5,827.66	926.36	651.28	1,131.96	2.53	-2.53	0.63
6,091.00	11.80	39.50	5,919.43	942.22	664.01	1,152.29	1.52	-1.49	1.49
6,186.00	9.00	38.70	6,012.86	955.52	674.84	1,169.42	2.95	-2.95	-0.84
6,281.00	6.60	39.30	6,106.98	965.54	682.94	1,182.30	2.53	-2.53	0.63
6,376.00	4.50	37.90	6,201.52	972.71	688.69	1,191.48	2.21	-2.21	-1.47
6,471.00	2.30	48.20	6,296.35	976.92	692.40	1,197.08	2.39	-2.32	10.84
6,566.00	1.10	75.00	6,391.31	978.43	694.71	1,199.66	1.48	-1.26	28.21
6,661.00	1.10	82.40	6,486.29	978.79	696.49	1,201.01	0.15	0.00	7.79
6,756.00	1.10	99.70	6,581.28	978.75	698.29	1,202.06	0.35	0.00	18.21
6,851.00	0.80	136.00	6,676.26	978.12	699.65	1,202.37	0.69	-0.32	38.21
6,947.00	1.10	138.70	6,772.25	976.95	700.73	1,202.07	0.32	0.31	2.81
7,042.00	1.20	147.60	6,867.23	975.42	701.86	1,201.52	0.22	0.11	9.37
7,137.00	1.30	145.20	6,962.21	973.70	703.01	1,200.83	0.12	0.11	-2.53
7,232.00	2.30	170.50	7,057.16	970.93	703.94	1,199.16	1.32	1.05	26.63
7,327.00	2.50	156.00	7,152.08	967.16	705.10	1,196.83	0.67	0.21	-15.26
7,398.00	1.85	144.36	7,223.03	964.81	706.39	1,195.72	1.10	-0.92	-16.39
7,468.00	1.67	62.18	7,293.00	964.37	707.95	1,196.30	3.31	-0.26	-117.40
7,526.00	1.85	57.79	7,350.98	965.27	709.49	1,197.94	0.39	0.31	-7.57
7,558.00	1.76	51.37	7,382.96	965.85	710.32	1,198.90	0.69	-0.28	-20.06
7,590.00	1.67	62.88	7,414.95	966.37	711.11	1,199.79	1.11	-0.28	35.97
7,622.00	1.85	71.70	7,446.93	966.74	712.02	1,200.63	1.01	0.56	27.56
7,653.00	1.41	80.55	7,477.92	966.96	712.87	1,201.32	1.63	-1.42	28.55
7,686.00	1.32	87.05	7,510.91	967.05	713.65	1,201.85	0.54	-0.27	19.70
7,717.00	1.49	78.70	7,541.90	967.14	714.40	1,202.38	0.86	0.55	-26.94
7,753.00	1.14	86.17	7,577.89	967.26	715.22	1,202.96	1.08	-0.97	20.75
7,784.00	1.14	88.64	7,608.88	967.29	715.84	1,203.35	0.16	0.00	7.97
7,812.00	1.14	81.50	7,636.88	967.34	716.39	1,203.72	0.51	0.00	-25.50
7,845.00	1.14	85.91	7,669.87	967.41	717.04	1,204.17	0.27	0.00	13.36
7,876.00	1.32	90.04	7,700.87	967.43	717.71	1,204.58	0.65	0.58	13.32
7,908.00	1.15	105.17	7,732.86	967.35	718.38	1,204.92	1.14	-0.53	47.28
7,940.00	1.14	102.96	7,764.85	967.19	719.00	1,205.16	0.14	-0.03	-6.91

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	SDI OH	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	OH	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
7,973.00	1.14	82.31	7,797.85	967.16	719.65	1,205.53	1.24	0.00	-62.58
8,003.00	1.41	73.34	7,827.84	967.31	720.30	1,206.03	1.12	0.90	-29.90
8,038.00	1.32	67.28	7,862.83	967.59	721.08	1,206.72	0.49	-0.26	-17.31
8,068.00	1.23	76.33	7,892.82	967.79	721.72	1,207.27	0.73	-0.30	30.17
8,095.00	1.32	75.36	7,919.81	967.94	722.30	1,207.74	0.34	0.33	-3.59
8,129.00	1.06	89.34	7,953.81	968.04	722.99	1,208.23	1.14	-0.76	41.12
8,159.00	0.97	88.55	7,983.80	968.05	723.52	1,208.56	0.30	-0.30	-2.63
8,191.00	0.97	94.52	8,015.80	968.04	724.06	1,208.87	0.32	0.00	18.66
8,226.00	1.06	102.52	8,050.79	967.95	724.67	1,209.16	0.48	0.26	22.86
8,252.00	1.06	110.70	8,076.79	967.81	725.13	1,209.32	0.58	0.00	31.46
8,285.00	1.23	105.77	8,109.78	967.60	725.76	1,209.53	0.59	0.52	-14.94
8,325.00	0.88	99.45	8,149.77	967.44	726.48	1,209.83	0.92	-0.88	-15.80
8,349.00	0.70	66.84	8,173.77	967.47	726.79	1,210.04	1.98	-0.75	-135.88
8,381.00	0.73	31.42	8,205.77	967.72	727.08	1,210.41	1.36	0.09	-110.69
8,414.00	0.70	70.09	8,238.77	967.96	727.38	1,210.79	1.44	-0.09	117.18
8,445.00	0.53	92.59	8,269.77	968.02	727.70	1,211.03	0.94	-0.55	72.58
8,477.00	0.44	60.54	8,301.76	968.08	727.95	1,211.22	0.88	-0.28	-100.16
8,514.00	0.62	96.28	8,338.76	968.12	728.28	1,211.45	0.99	0.49	96.59
8,545.00	0.79	81.69	8,369.76	968.14	728.66	1,211.69	0.79	0.55	-47.06
8,571.00	0.88	87.93	8,395.76	968.17	729.03	1,211.94	0.49	0.35	24.00
8,609.00	0.88	103.14	8,433.75	968.11	729.61	1,212.24	0.61	0.00	40.03
8,639.00	0.88	108.41	8,463.75	967.99	730.05	1,212.41	0.27	0.00	17.57
8,666.00	1.06	106.30	8,490.75	967.85	730.49	1,212.56	0.68	0.67	-7.81
8,702.00	0.70	78.35	8,526.74	967.80	731.02	1,212.84	1.53	-1.00	-77.64
8,728.00	0.53	86.26	8,552.74	967.84	731.30	1,213.03	0.73	-0.65	30.42
8,761.00	0.53	118.34	8,585.74	967.78	731.58	1,213.16	0.89	0.00	97.21
8,795.00	0.35	321.46	8,619.74	967.79	731.66	1,213.20	2.54	-0.53	-461.41
8,828.00	0.62	312.93	8,652.74	967.99	731.46	1,213.25	0.84	0.82	-25.85
8,857.00	0.79	321.02	8,681.74	968.25	731.22	1,213.32	0.68	0.59	27.90
8,887.00	0.62	302.56	8,711.73	968.50	730.96	1,213.36	0.94	-0.57	-61.53
8,922.00	0.53	295.62	8,746.73	968.67	730.65	1,213.31	0.32	-0.26	-19.83
8,953.00	0.44	270.04	8,777.73	968.73	730.40	1,213.21	0.75	-0.29	-82.52
8,987.00	0.53	281.47	8,811.73	968.76	730.12	1,213.07	0.39	0.26	33.62
9,017.00	0.53	276.02	8,841.73	968.81	729.84	1,212.94	0.17	0.00	-18.17
9,050.00	0.79	273.03	8,874.73	968.83	729.47	1,212.73	0.79	0.79	-9.06
9,082.00	0.62	276.90	8,906.72	968.87	729.07	1,212.53	0.55	-0.53	12.09
9,114.00	0.53	251.32	8,938.72	968.84	728.76	1,212.32	0.84	-0.28	-79.94
9,143.00	0.90	258.92	8,967.72	968.75	728.41	1,212.04	1.31	1.28	26.21
9,174.00	0.62	260.20	8,998.72	968.68	728.01	1,211.74	0.90	-0.90	4.13
9,211.00	0.62	238.14	9,035.71	968.54	727.64	1,211.41	0.64	0.00	-59.62
9,240.00	0.53	227.94	9,064.71	968.37	727.41	1,211.13	0.47	-0.31	-35.17
9,269.00	0.79	226.27	9,093.71	968.14	727.16	1,210.80	0.90	0.90	-5.76
9,305.00	0.97	227.33	9,129.71	967.76	726.76	1,210.25	0.50	0.50	2.94
9,333.00	1.09	224.17	9,157.70	967.41	726.40	1,209.76	0.47	0.43	-11.29

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

<b>Project</b>	Uintah County, UT NAD27		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

Site	Desert Springs				
Site Position:		Northing:	607,976.71 usft	Latitude:	39° 59' 26.380 N
From:	Lat/Long	Easting:	2,466,005.55 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	1.07 °

Well	Desert Springs State #412-36-9-18					
Well Position	+N/-S	0.00 ft	Northing:	607,976.68 usft	Latitude:	39° 59' 26.379 N
	+E/-W	0.00 ft	Easting:	2,466,005.56 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	0.00 ft	Ground Level:	4,912.00 ft

<b>Wellbore</b>	ST-1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	BGGM2014	7/11/2014	10.94	65.71	51,865

<b>Design</b>	ST-1				
<b>Audit Notes:</b>					
<b>Version:</b>	1.0	<b>Phase:</b>	ACTUAL	<b>Tie On Depth:</b>	3,560.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>	
	0.00	0.00	0.00	38.85	

<b>Survey Program</b>	<b>Date</b>	8/20/2014			
<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>	
145.00	2,990.00	Survey #1 (GyroData OH)	MWD	MWD - Standard	
2,990.00	3,560.00	Survey #1 - MWD Survey (SDI OH)	MWD	MWD - Standard	
3,560.00	11,525.00	Survey #1 - Production MWD Survey (ST-	SDI MWD	SDI MWD - Standard ver 1.0.1	

<b>Survey</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Vertical Section (ft)</b>	<b>Dogleg Rate (°/100ft)</b>	<b>Build Rate (°/100ft)</b>	<b>Turn Rate (°/100ft)</b>	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
145.00	0.92	328.48	144.99	0.99	-0.61	0.39	0.63	0.63	0.00	
237.00	0.92	334.19	236.98	2.29	-1.32	0.96	0.10	0.00	6.21	
329.00	2.95	28.33	328.93	5.04	-0.51	3.60	2.74	2.21	58.85	
425.00	6.33	38.61	424.60	11.35	3.96	11.32	3.61	3.52	10.71	
519.00	6.99	40.81	517.97	19.73	10.93	22.22	0.75	0.70	2.34	
612.00	6.24	38.70	610.35	27.95	17.79	32.93	0.85	-0.81	-2.27	
706.00	5.19	41.34	703.88	35.13	23.79	42.29	1.15	-1.12	2.81	
800.00	5.05	42.92	797.51	41.36	29.42	50.66	0.21	-0.15	1.68	

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

<b>Project</b>	Uintah County, UT NAD27		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

Site	Desert Springs				
Site Position:		Northing:	607,976.71 usft	Latitude:	39° 59' 26.380 N
From:	Lat/Long	Easting:	2,466,005.55 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	1.07 °

Well		Desert Springs State #412-36-9-18				
Well Position	+N/-S	0.00 ft	Northing:	607,976.68 usft	Latitude:	39° 59' 26.379 N
	+E/-W	0.00 ft	Easting:	2,466,005.56 usft	Longitude:	109° 50' 12.030 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	0.00 ft	Ground Level:	4,912.00 ft

<b>Wellbore</b>	ST-1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	BGGM2014	7/11/2014	10.94	65.71	51,865

<b>Design</b>	ST-1				
<b>Audit Notes:</b>					
<b>Version:</b>	1.0	<b>Phase:</b>	ACTUAL	<b>Tie On Depth:</b>	3,560.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>	
	0.00	0.00	0.00	38.85	

<b>Survey Program</b>	<b>Date</b>	9/22/2014			
<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>	
145.00	2,990.00	Survey #1 (GyroData OH)	MWD	MWD - Standard	
2,990.00	3,560.00	Survey #1 - MWD Survey (SDI OH)	MWD	MWD - Standard	
3,560.00	12,785.00	Survey #1 - Production MWD Survey (ST-	SDI MWD	SDI MWD - Standard ver 1.0.1	

<b>Survey</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Vertical Section (ft)</b>	<b>Dogleg Rate (°/100ft)</b>	<b>Build Rate (°/100ft)</b>	<b>Turn Rate (°/100ft)</b>	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
145.00	0.92	328.48	144.99	0.99	-0.61	0.39	0.63	0.63	0.00	
237.00	0.92	334.19	236.98	2.29	-1.32	0.96	0.10	0.00	6.21	
329.00	2.95	28.33	328.93	5.04	-0.51	3.60	2.74	2.21	58.85	
425.00	6.33	38.61	424.60	11.35	3.96	11.32	3.61	3.52	10.71	
519.00	6.99	40.81	517.97	19.73	10.93	22.22	0.75	0.70	2.34	
612.00	6.24	38.70	610.35	27.95	17.79	32.93	0.85	-0.81	-2.27	
706.00	5.19	41.34	703.88	35.13	23.79	42.29	1.15	-1.12	2.81	
800.00	5.05	42.92	797.51	41.36	29.42	50.66	0.21	-0.15	1.68	



## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
895.00	5.19	43.80	892.13	47.52	35.24	59.11	0.17	0.15	0.93
989.00	4.84	32.55	985.77	53.93	40.32	67.29	1.11	-0.37	-11.97
1,083.00	4.57	33.69	1,079.45	60.39	44.53	74.96	0.30	-0.29	1.21
1,182.00	4.18	34.66	1,178.16	66.64	48.77	82.49	0.40	-0.39	0.98
1,274.00	5.01	35.63	1,269.87	72.66	53.02	89.84	0.91	0.90	1.05
1,369.00	5.67	36.42	1,364.45	79.81	58.22	98.67	0.70	0.69	0.83
1,461.00	5.71	36.50	1,456.00	87.14	63.64	107.79	0.04	0.04	0.09
1,556.00	5.89	37.12	1,550.51	94.83	69.39	117.38	0.20	0.19	0.65
1,650.00	6.29	36.24	1,643.98	102.83	75.35	127.35	0.44	0.43	-0.94
1,744.00	6.29	32.90	1,737.42	111.31	81.19	137.61	0.39	0.00	-3.55
1,839.00	6.20	30.53	1,831.85	120.09	86.62	147.86	0.29	-0.09	-2.49
1,934.00	6.24	31.49	1,926.29	128.92	91.92	158.06	0.12	0.04	1.01
2,030.00	5.63	29.38	2,021.78	137.47	96.96	167.88	0.67	-0.64	-2.20
2,126.00	5.14	31.23	2,117.36	145.25	101.50	176.79	0.54	-0.51	1.93
2,220.00	4.88	33.78	2,211.00	152.17	105.90	184.94	0.36	-0.28	2.71
2,316.00	5.71	31.49	2,306.59	159.64	110.67	193.75	0.89	0.86	-2.39
2,408.00	5.63	34.22	2,398.14	167.27	115.60	202.78	0.31	-0.09	2.97
2,503.00	5.67	36.33	2,492.68	174.91	121.00	212.12	0.22	0.04	2.22
2,599.00	5.63	35.10	2,588.21	182.58	126.52	221.55	0.13	-0.04	-1.28
2,692.00	5.67	32.99	2,680.76	190.17	131.64	230.68	0.23	0.04	-2.27
2,788.00	5.85	39.58	2,776.27	197.91	137.34	240.28	0.71	0.19	6.86
2,879.00	5.67	40.46	2,866.81	204.91	143.21	249.42	0.22	-0.20	0.97
2,971.00	5.41	38.35	2,958.38	211.77	148.85	258.30	0.36	-0.28	-2.29
2,990.00	5.36	38.09	2,977.30	213.17	149.96	260.08	0.29	-0.26	-1.37
3,052.00	5.30	38.70	3,039.03	217.68	153.53	265.84	0.13	-0.10	0.98
3,147.00	4.70	37.60	3,133.67	224.19	158.65	274.12	0.64	-0.63	-1.16
3,242.00	5.70	30.00	3,228.28	231.36	163.38	282.67	1.28	1.05	-8.00
3,337.00	5.40	27.00	3,322.83	239.43	167.77	291.71	0.44	-0.32	-3.16
3,432.00	5.40	31.30	3,417.41	247.23	172.12	300.51	0.43	0.00	4.53
3,527.00	6.30	38.40	3,511.92	255.14	177.68	310.16	1.21	0.95	7.47
3,560.00	6.74	41.02	3,544.71	258.02	180.08	313.90	1.61	1.34	7.93
3,572.00	5.54	46.18	3,556.64	258.95	180.96	315.18	11.00	-10.01	43.02
First SDI Production MWD Survey									
3,635.00	6.07	54.27	3,619.31	263.00	185.86	321.41	1.55	0.84	12.84
3,730.00	6.95	53.74	3,713.70	269.33	194.57	331.80	0.93	0.93	-0.56
3,825.00	8.56	54.31	3,807.83	276.86	204.95	344.17	1.70	1.69	0.60
3,920.00	9.12	51.37	3,901.70	285.68	216.57	358.34	0.76	0.59	-3.09
4,015.00	9.86	53.68	3,995.40	295.20	229.01	373.55	0.88	0.78	2.43
4,107.00	11.17	53.30	4,085.85	305.19	242.50	389.80	1.43	1.42	-0.41
4,202.00	11.78	53.57	4,178.95	316.45	257.68	408.09	0.64	0.64	0.28
4,297.00	13.45	54.18	4,271.66	328.68	274.44	428.12	1.76	1.76	0.64
4,393.00	15.83	53.04	4,364.53	343.08	293.96	451.59	2.50	2.48	-1.19
4,488.00	16.38	53.83	4,455.81	358.78	315.13	477.09	0.62	0.58	0.83

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,583.00	16.27	49.96	4,546.98	375.25	336.13	503.09	1.15	-0.12	-4.07
4,679.00	18.99	48.56	4,638.46	394.24	358.14	531.69	2.87	2.83	-1.46
4,774.00	19.79	50.93	4,728.07	414.61	382.21	562.65	1.18	0.84	2.49
4,870.00	20.40	49.79	4,818.23	435.65	407.61	594.97	0.76	0.64	-1.19
4,965.00	20.05	48.38	4,907.37	457.16	432.43	627.29	0.63	-0.37	-1.48
5,059.00	19.43	47.77	4,995.85	478.37	456.05	658.63	0.70	-0.66	-0.65
5,155.00	18.38	45.74	5,086.67	499.66	478.71	689.43	1.29	-1.09	-2.11
5,250.00	16.95	45.95	5,177.19	519.75	499.39	718.04	1.51	-1.51	0.22
5,345.00	17.76	48.03	5,267.86	539.07	520.12	746.09	1.07	0.85	2.19
5,440.00	18.40	45.92	5,358.17	559.19	541.66	775.27	0.96	0.67	-2.22
5,535.00	18.65	43.46	5,448.25	580.64	562.88	805.29	0.86	0.26	-2.59
5,630.00	17.69	38.12	5,538.52	603.02	582.24	834.87	2.02	-1.01	-5.62
5,725.00	17.32	30.91	5,629.13	626.52	598.42	863.31	2.31	-0.39	-7.59
5,820.00	18.23	30.43	5,719.59	651.46	613.21	892.01	0.97	0.96	-0.51
5,916.00	16.80	31.59	5,811.14	676.23	628.08	920.63	1.53	-1.49	1.21
6,011.00	16.18	30.01	5,902.23	699.38	641.90	947.33	0.81	-0.65	-1.66
6,105.00	15.83	26.23	5,992.59	722.23	654.11	972.78	1.17	-0.37	-4.02
6,200.00	16.71	28.17	6,083.79	745.89	666.29	998.85	1.09	0.93	2.04
6,295.00	16.27	26.85	6,174.88	769.80	678.75	1,025.29	0.61	-0.46	-1.39
6,389.00	16.63	25.90	6,265.03	793.65	690.57	1,051.27	0.48	0.38	-1.01
6,484.00	15.30	26.32	6,356.37	817.12	702.07	1,076.76	1.41	-1.40	0.44
6,580.00	15.83	27.73	6,448.85	840.06	713.77	1,101.97	0.68	0.55	1.47
6,675.00	13.72	29.40	6,540.70	861.35	725.33	1,125.80	2.27	-2.22	1.76
6,770.00	12.93	28.96	6,633.14	880.46	736.01	1,147.38	0.84	-0.83	-0.46
6,865.00	10.69	26.85	6,726.13	897.62	745.14	1,166.48	2.40	-2.36	-2.22
6,960.00	9.58	28.34	6,819.64	912.44	752.87	1,182.87	1.20	-1.17	1.57
7,055.00	8.37	18.79	6,913.48	925.95	758.85	1,197.14	2.02	-1.27	-10.05
7,150.00	7.17	10.24	7,007.61	938.33	762.13	1,208.84	1.75	-1.26	-9.00
7,246.00	4.66	9.27	7,103.09	948.07	763.83	1,217.49	2.62	-2.61	-1.01
7,341.00	3.18	345.46	7,197.87	954.43	763.79	1,222.42	2.28	-1.56	-25.06
7,436.00	2.38	344.74	7,292.76	958.89	762.61	1,225.14	0.84	-0.84	-0.76
7,530.00	1.41	348.62	7,386.71	961.90	761.86	1,227.03	1.04	-1.03	4.13
7,626.00	1.06	332.62	7,482.69	963.85	761.22	1,228.14	0.51	-0.36	-16.67
7,721.00	0.88	320.84	7,577.67	965.20	760.36	1,228.65	0.28	-0.19	-12.40
7,816.00	0.53	309.94	7,672.67	966.04	759.56	1,228.81	0.39	-0.37	-11.47
7,911.00	0.53	274.61	7,767.66	966.36	758.78	1,228.57	0.34	0.00	-37.19
8,005.00	0.44	260.81	7,861.66	966.34	758.00	1,228.05	0.16	-0.10	-14.68
8,101.00	0.70	234.80	7,957.65	965.94	757.15	1,227.22	0.38	0.27	-27.09
8,194.00	0.70	210.10	8,050.65	965.12	756.40	1,226.11	0.32	0.00	-26.56
8,289.00	1.06	223.02	8,145.64	963.98	755.51	1,224.66	0.43	0.38	13.60
8,385.00	0.79	198.85	8,241.62	962.70	754.69	1,223.15	0.49	-0.28	-25.18
8,480.00	1.32	209.75	8,336.61	961.13	753.94	1,221.45	0.59	0.56	11.47
8,575.00	0.44	150.77	8,431.60	959.87	753.57	1,220.24	1.22	-0.93	-62.08
8,670.00	0.93	150.53	8,526.59	958.88	754.13	1,219.82	0.52	0.52	-0.25

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,765.00	1.14	65.87	8,621.58	958.59	755.37	1,220.37	1.48	0.22	-89.12
8,861.00	1.32	78.70	8,717.56	959.20	757.33	1,222.07	0.34	0.19	13.36
8,956.00	1.06	105.16	8,812.54	959.18	759.25	1,223.27	0.63	-0.27	27.85
9,051.00	1.06	87.64	8,907.52	958.99	760.98	1,224.20	0.34	0.00	-18.44
9,147.00	0.88	119.85	9,003.51	958.66	762.50	1,224.90	0.59	-0.19	33.55
9,242.00	1.30	113.79	9,098.49	957.86	764.12	1,225.29	0.46	0.44	-6.38
9,337.00	0.62	101.56	9,193.48	957.32	765.61	1,225.81	0.74	-0.72	-12.87
9,433.00	0.88	133.28	9,289.47	956.71	766.66	1,225.99	0.50	0.27	33.04
9,528.00	0.43	146.98	9,384.46	955.91	767.38	1,225.82	0.50	-0.47	14.42
9,623.00	0.26	124.58	9,479.46	955.49	767.75	1,225.73	0.23	-0.18	-23.58
9,719.00	0.53	140.40	9,575.46	955.03	768.22	1,225.66	0.30	0.28	16.48
9,813.00	0.72	286.41	9,669.46	954.86	767.93	1,225.34	1.27	0.20	155.33
9,908.00	0.97	283.75	9,764.45	955.22	766.57	1,224.77	0.27	0.26	-2.80
10,003.00	0.26	352.66	9,859.44	955.62	765.76	1,224.58	0.96	-0.75	72.54
10,098.00	0.40	163.74	9,954.44	955.52	765.83	1,224.54	0.69	0.15	180.08
10,194.00	0.79	306.43	10,050.44	955.59	765.39	1,224.32	1.18	0.41	148.64
10,289.00	0.88	289.11	10,145.43	956.22	764.17	1,224.05	0.28	0.09	-18.23
10,384.00	0.79	250.00	10,240.42	956.23	762.87	1,223.24	0.60	-0.09	-41.17
10,480.00	0.62	11.56	10,336.41	956.52	762.35	1,223.14	1.28	-0.18	126.63
10,575.00	0.18	3.38	10,431.41	957.17	762.46	1,223.71	0.47	-0.46	-8.61
10,670.00	0.09	136.18	10,526.41	957.26	762.52	1,223.83	0.26	-0.09	139.79
10,766.00	0.26	115.00	10,622.41	957.12	762.77	1,223.87	0.19	0.18	-22.06
10,861.00	0.18	152.62	10,717.41	956.89	763.04	1,223.86	0.17	-0.08	39.60
10,956.00	0.26	54.18	10,812.41	956.89	763.28	1,224.01	0.36	0.08	-103.62
11,049.00	0.79	172.83	10,905.41	956.37	763.53	1,223.77	1.01	0.57	127.58
11,145.00	0.44	156.57	11,001.40	955.38	763.76	1,223.14	0.40	-0.36	-16.94
11,240.00	0.70	82.83	11,096.40	955.12	764.48	1,223.38	0.75	0.27	-77.62
11,335.00	0.53	97.42	11,191.39	955.13	765.49	1,224.03	0.24	-0.18	15.36
11,430.00	1.23	117.73	11,286.38	954.60	766.83	1,224.46	0.80	0.74	21.38
11,525.00	0.88	148.93	11,381.36	953.50	768.11	1,224.40	0.69	-0.37	32.84
11,620.00	1.23	154.11	11,476.35	951.96	768.93	1,223.72	0.38	0.37	5.45
11,716.00	0.88	277.07	11,572.34	951.12	768.65	1,222.89	1.94	-0.36	128.08
11,811.00	0.79	283.66	11,667.33	951.37	767.29	1,222.23	0.14	-0.09	6.94
11,906.00	0.53	285.07	11,762.32	951.64	766.23	1,221.77	0.27	-0.27	1.48
12,001.00	0.59	266.91	11,857.32	951.73	765.32	1,221.27	0.20	0.06	-19.12
12,095.00	0.79	284.28	11,951.31	951.86	764.21	1,220.67	0.31	0.21	18.48
12,191.00	0.62	273.29	12,047.31	952.05	763.05	1,220.10	0.23	-0.18	-11.45
12,286.00	0.53	286.92	12,142.30	952.21	762.11	1,219.63	0.17	-0.09	14.35
12,381.00	0.44	258.00	12,237.30	952.26	761.34	1,219.19	0.27	-0.09	-30.44
12,485.00	0.62	220.12	12,341.29	951.75	760.58	1,218.31	0.37	0.17	-36.42
12,580.00	0.77	200.67	12,436.29	950.76	760.03	1,217.19	0.29	0.16	-20.47
12,675.00	0.66	208.19	12,531.28	949.68	759.54	1,216.05	0.15	-0.12	7.92
12,730.00	0.79	201.57	12,586.27	949.05	759.25	1,215.38	0.28	0.24	-12.04

## Survey Report



<b>Company:</b>	Gasco Energy	<b>Local Co-ordinate Reference:</b>	Well Desert Springs State #412-36-9-18
<b>Project:</b>	Uintah County, UT NAD27	<b>TVD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Site:</b>	Desert Springs	<b>MD Reference:</b>	GL 4912' & RKB 25' @ 4937.00ft (SST 54)
<b>Well:</b>	Desert Springs State #412-36-9-18	<b>North Reference:</b>	True
<b>Wellbore:</b>	ST-1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	ST-1	<b>Database:</b>	Grand Junction District

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
<b>Last SDI Production MWD Survey</b>									
12,785.00	0.79	201.57	12,641.27	948.34	758.97	1,214.65	0.00	0.00	0.00
<b>Projection to Bit</b>									

Design Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
3,572.00	3,556.64	258.95	180.96	First SDI Production MWD Survey
12,730.00	12,586.27	949.05	759.25	Last SDI Production MWD Survey
12,785.00	12,641.27	948.34	758.97	Projection to Bit

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



Effective Date: 4/16/2015

<b>FORMER OPERATOR:</b>	<b>NEW OPERATOR:</b>
Gasco Production Company N2575 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805	Badlands Production Company N4265 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805
CA Number(s):	Unit(s): Gate Canyon, Wilkin Ridge Deep, RBU-EOR-GRRV

**WELL INFORMATION:**

Well Name	Sec	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
See Attached List									

**OPERATOR CHANGES DOCUMENTATION:**

1. Sundry or legal documentation was received from the **FORMER** operator on: 6/2/2015
2. Sundry or legal documentation was received from the **NEW** operator on: 6/2/2015
3. New operator Division of Corporations Business Number: 1454161-0143

**REVIEW:**

1. Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: 6/2/2015
2. Receipt of Acceptance of Drilling Procedures for APD on: N/A
3. Reports current for Production/Disposition & Sundries: 6/3/2015
4. OPS/SI/TA well(s) reviewed for full cost bonding: 1/20/2016
5. UIC5 on all disposal/injection/storage well(s) approved on: N/A
6. Surface Facility(s) included in operator change: None
7. Inspections of PA state/fee well sites complete on (only upon operators request): N/A

**NEW OPERATOR BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: SUR0027842
2. Indian well(s) covered by Bond Number: N/A
3. State/fee well(s) covered by Bond Number(s): SUR0027845  
SUR0035619 -FCB

**DATA ENTRY:**

1. Well(s) update in the **OGIS** on: 1/22/2016
2. Entity Number(s) updated in **OGIS** on: 1/22/2016
3. Unit(s) operator number update in **OGIS** on: 1/22/2016
4. Surface Facilities update in **OGIS** on: N/A
5. State/Fee well(s) attached to bond(s) in **RBDMS** on: 1/22/2016
6. Surface Facilities update in **RBDMS** on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

1. The **NEW** operator of the Fee (Mineral) wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/22/2016

**COMMENTS:**

From: Gasco Production Company  
To: Badlands Production Company  
Effective Date: 4/16/2015

Well Name	Section	TWN	RNG	API Number	Entity	Mineral	Surface	Type	Status
FEDERAL 23-18G-9-19	18	090S	190E	4304752496		Federal	Federal	OW	APD
FEDERAL 14-17G-9-19	17	090S	190E	4304752522		Federal	Federal	OW	APD
FEDERAL 13-18G-9-19	18	090S	190E	4304752538		Federal	Federal	OW	APD
FEDERAL 23-29G-9-19	29	090S	190E	4304752544		Federal	Federal	OW	APD
FEDERAL 24-20G-9-19	20	090S	190E	4304752545		Federal	Federal	OW	APD
FEDERAL 31-21G-9-19	21	090S	190E	4304752546		Federal	Federal	OW	APD
Federal 323-29-9-19	29	090S	190E	4304753026		Federal	Federal	GW	APD
Federal 421-29-9-19	29	090S	190E	4304753027		Federal	Federal	GW	APD
Federal 322-29-9-19	29	090S	190E	4304753029		Federal	Federal	GW	APD
Federal 431-29-9-19	29	090S	190E	4304753030		Federal	Federal	GW	APD
Federal 432-29-9-19	29	090S	190E	4304753031		Federal	Federal	GW	APD
Federal 414-29-9-19	29	090S	190E	4304753070		Federal	Federal	GW	APD
FEDERAL 412-29-9-19	29	090S	190E	4304753073		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753076		Federal	Federal	GW	APD
federal 321-29-9-19	29	090S	190E	4304753078		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753079		Federal	Federal	GW	APD
FEDERAL 321-29-9-19	29	090S	190E	4304753080		Federal	Federal	GW	APD
Federal 212-29-9-19	29	090S	190E	4304753133		Federal	Federal	GW	APD
State 321-32-9-19	32	090S	190E	4304754479		State	State	GW	APD
State 423-32-9-19	32	090S	190E	4304754480		State	State	GW	APD
State 421-32-9-19	32	090S	190E	4304754481		State	State	GW	APD
State 413-32-9-19	32	090S	190E	4304754482		State	State	GW	APD
State 323-32-9-19	32	090S	190E	4304754483		State	State	GW	APD
State 431-32-9-19	32	090S	190E	4304754529		State	State	GW	APD
Desert Spring State 224-36-9-18	36	090S	180E	4304754541		State	State	GW	APD
Desert Spring State 243-36-9-18	36	090S	180E	4304754542		State	State	GW	APD
Desert Spring State 241-36-9-18	36	090S	180E	4304754543		State	State	GW	APD
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	P
RBV 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P

From: Gasco Production Company  
To: Badlands Production Company  
Effective Date: 4/16/2015

RBU 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBU 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBU 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBU 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBU 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBU 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBU 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBU 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBU 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBU 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P
FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P

From: Gasco Production Company  
To: Badlands Production Company  
Effective Date: 4/16/2015

SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P
LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S



From: Gasco Production Company  
To: Badlands Production Company  
Effective Date: 4/16/2015

RBU 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBU 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBU 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-76482
2. NAME OF OPERATOR: Gasco Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 7979 E. Tufts Ave. CITY Denver STATE CO ZIP 80237		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (303) 483-0044		8. WELL NAME and NUMBER: Desert Spring Fed 21-1-10-18
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0633 FNL 1512 FWL		9. API NUMBER: 4304737631
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 1 10S 18E S		10. FIELD AND POOL, OR WILDCAT: Uteland Butte

COUNTY: Uintah

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/16/2015	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco Production Company requests a change of operator on this well, in addition to the wells on the attached list from Gasco Production Company to Badlands Production Company, effective date of 4/16/2015.

Gasco Production Company  
7979 E Tufts Ave, Suite 1150  
Denver CO 80237  
303-996-1805

Michael Decker, Exec. Vice President & COO

Badlands Production Company  
7979 E Tufts Ave, Suite 1150  
Denver CO 80237  
303-996-1805

Michael Decker, Exec. Vice President & COO

RECEIVED

JUN 02 2015

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Lindsey Cooke	TITLE Engineering Tech
SIGNATURE <i>Lindsey Cooke</i>	DATE 5/18/2015

(This space for State use only)

**APPROVED**

JAN 22 2016

DIV. OIL GAS & MINING  
BY: *Rachel Medina*

Well Name	Section	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
RBUS 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P
RBUS 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBUS 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBUS 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBUS 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBUS 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBUS 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBUS 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBUS 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBUS 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBUS 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P

FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P
SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P



LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S
RBW 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBW 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBW 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S